RANCHO SANTIAGO COMMUNITY COLLEGE DISTRICT



ADDENDUM NO. 1

Bid #1457 Roofing Repairs Project at Centennial Education Center

Address: 2900 West Edinger Avenue, Santa Ana, CA 92706

Project ID#2915

May 24, 2024

Owner: Rancho Santiago Community College District 2323 North Broadway, Room 112 Santa Ana, California 92706

Bid #1457 Roof Repair at Centennial Education Center Project ID #2915, Rancho Santiago Community College District Rev180907 Addendum No. 1 Page 1 of 3

RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED ON BID FORM WHEN SUBMITTED

The following changes, additions, deletions or corrections shall become a part of the Contract Documents for the project named on the previous page and all other conditions shall remain the same. The Bidders shall be responsible for transmitting this information to all affected Subcontractors and Suppliers, prior to the closing of Bids. Prospective Bidders shall acknowledge receipt of all Addenda in the space provided on the Bid Proposal Form by the number (list every addenda). Failure to do so shall deem the Bid Proposal as non-responsive and subject the Bidder to disqualification.

Item No. AD 1-1 Extension of Bid Due Date (see revised date in red)

Submittal of Bid Proposals. All Bid Proposals must be submitted on forms furnished by the District prior to 2:00 P.M., Wednesday, May 29, 2024, Wednesday, June 5, 2024 the last time for submission of Bid Proposals and the District's public opening and reading of Bid Proposals. Submit Bids to RSCCD Facility Planning, Construction and District Support Services at 2323 North Broadway, Suite 112, Santa Ana, CA 92706. Bidders are solely responsible for timely submission of Bid Proposals to the District at the designated location. The District shall not be responsible for any delays or issues with mail delivery. Any bid received after the scheduled closing time for receipt of bids shall be returned to the bidder unopened. Bid Summary will be posted on the District's website (www.rsccd.edu then click on "Bid Opportunities")

Item No. AD 1-2 Additional Clarification

Indicated overflow scupper on Building E shall be extended 6" to ensure draining water does not contact the T1-11 exterior siding.

Item No. AD 1-3 Additional Clarification

All existing downspouts shall be cleaned and inspected for any blockages for Roof Sections A, B, C, D, E, & F.

Item No. AD 1-4 Additional Scope of Work

Indicated gutter on Building C shall be removed and replaced. Gutters to match existing size, and design and fabricated from Garland flat stock with factory Kynar coating or approved equal. Slope gutters ¹/₄:12 to existing downspouts. Install expansion joints and seal seams of gutters as recommended by SMACNA. Color as approved by the owner.

Item No. AD 1-5 Specifications: Revise Item L in Existing Coated Modified Roof Sections – Roof Section A, B, C, D & F

Scuppers: Indicated scuppers on Building B and Building C shall be removed and replaced as necessary to ensure positive drainage. Replace damaged decking as approved 4 sq. ft. of existing roof membrane and wall membrane surrounding the indicated scupper areas shall be removed to the roof deck and replaced with StressPly IV Plus UV Mineral Torch sheet prior to application of the silicone membrane. The existing roof shall be cleaned and primed prior to torch application. Torch installation shall be performed per manufacturer approved detail. Torch membrane shall be solidly adhered to the existing roofing to the satisfaction of the membrane manufacturer. The goal

is to ensure the scupper and adjacent vertical and horizontal materials are in good condition, have positive slope to the drains and the existing roofing and wall membrane are in acceptable condition to accept the fluid-applied roofing materials.

Item No. AD 1-6 Specifications: Remove Item H in Existing Standing Seam Metal Roof Section – Roof Sections G, D106 – D112, & C110

Gutters: Only as indicated and approved, remove and replace existing gutters throughout the site. Gutters to match existing size, and design and fabricated from Garland flat stock with factory Kynar coating or approved equal. Slope gutters ¹/₄:12 to existing downspouts. Install expansion joints and seal seams of gutters as recommended by SMACNA. Color as approved by the owner.

Item No. AD 1-7 Additional Clarification: Existing Standing Seam Metal Roof Section – Roof Sections G, D106 – D112, & C110

All existing gutters and downspouts shall be cleaned and inspected for any blockages.

Item No. AD 1-8 Updated Map

CEC Site Map

Item No. AD 1-9 Hazardous Material Survey

Enclosed for your information a Limited Asbestos and Lead Survey and Hazardous Materials Abatement Specification for the roofing repair project at the Centennial Education Center

Enc: Hazardous Materials Survey and Specifications Centennial Education Center Map

This is the end of Addendum No. 1



LIMITED ASBESTOS AND LEAD SURVEY

May 10, 2024

Prepared For:

Rancho Santiago Community College District Ms. Ava Hill 2323 North Broadway Santa Ana, CA 92706

NV5

NV5 – Alta Environmental 3777 Long Beach Blvd, Annex Building Long Beach, CA 90807 Phone: 562.495.5777

RSCC-24-12223

NV5

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	PROJECT BACKGROUND	1
3.0	PROJECT BACKGROUND	1
4.0	METHODOLOGY	1
4.1 4.2	ASBESTOS LEAD	1 2
5.0	RESULTS	2
5.1 5.2	ASBESTOS LEAD	2 4
6.0	CONCLUSION AND RECOMMENDATIONS	4
6.1 6.2	ASBESTOS LEAD	4 5
7.0	ASSUMPTIONS AND LIMITATIONS	5
80	SIGNATORY	6

APPENDICES

Appendix A: Material Inventory: Asbestos and Lead Appendix B: Laboratory Analytical Report and Field Notes: Asbestos and Lead Appendix C: Sample Location Map: Asbestos and Lead Appendix D: NV5 Employee and Laboratory Certifications

N|V|5

1.0 INTRODUCTION

On May 4, 2024, NV5 conducted an investigation for the presence of asbestos-containing materials (ACM) and lead based paint from the roofs at Centennial Education Center Buildings A, B, C, D, E, F, G, Portables C110, C111, D106 thru D112, and the shed at C111 located at 2900 West Edinger Avenue Street, Santa Ana, CA 92704.

2.0 PROJECT BACKGROUND

Rancho Santiago Community College District located in Santa Ana, California 92706, retained NV5 for this investigation. Eric Fleming, a Cal/OSHA Certified Asbestos Consultant and California Department of Public Health (CDPH) Certified Lead Inspector/Assessor employed by NV5 conducted the sampling.

3.0 PROJECT BACKGROUND

The survey included the following:

- Initial investigation to locate suspect ACM and lead based paint
- Physical assessment of suspect materials
- Collection of bulk samples and paint chip samples from suspect materials and painted surfaces
- Laboratory analysis of all collected samples.

4.0 METHODOLOGY

4.1 ASBESTOS

The sampling was conducted using guidelines set forth in *Federal Register 40 CFR Part 763*. NV5 conducted an initial walkthrough of the site to develop a listing and sampling scheme of suspect materials. Samples were placed in sealable sample containers and assigned a unique sample identification number.

Bulk samples collected from the subject site were subsequently analyzed by polarized light microscopy (PLM) for asbestos content in accordance with the United States Environmental Protection Agency's (USEPA) *Determination of Asbestos in Bulk Building Materials: EPA/600/R-93/116, July 1993*, at AQ Environmental Laboratories, a laboratory accredited by the National Voluntary Laboratory Accreditation Program and located in Signal Hill, California.

Based on the requirements of the USEPA as set forth in *40 CFR* 763, a homogeneous area is defined as "an area of surfacing material, thermal system insulation material or miscellaneous material that is uniform in color and texture." Furthermore, the regulation requires that a minimum number of



samples be collected from each identified homogeneous area. If one sample in a homogeneous area is found to contain asbestos, the entire homogeneous area is asbestos containing.

It is possible that one sample out of a set of samples collected from a homogeneous area can be positive for asbestos and the remaining samples in the homogeneous area are negative. However, the entire area must be considered asbestos-containing.

Caution is advised in interpreting results provided herein.

The survey was conducted to identify hazardous materials (asbestos and lead) prior to demolition of the structures. As such, all areas were investigated (including interstitial wall and ceiling spaces). There were no inaccessible areas. However, an investigation below soil grade was outside the scope of this project, and additional material such as asbestos-cement pipes, electrical wiring insulation, or other materials may subsequently be discovered.

4.2 **LEAD**

Paint chips were collected to determine the weight percent concentration of lead in the painted surfaces. Paint chip samples were collected for construction safety as defined by *Title 8 CCR* Section 1532.1. Paint chip sample analysis was conducted by EPA Method SW846/7420 at AQ Environmental Laboratories, a laboratory accredited by the Environmental Laboratory Accreditation Program and located in Signal Hill, California.

5.0 **RESULTS**

5.1 ASBESTOS

Material	Sample No.	Material Location	Asbestos Content
		Building A	
White and black roof mastic	8550 - 8552	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	5% chrysotile
		Building B	
White/black roof mastic	8527 - 8529	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	3% chrysotile
Rolled on roof core Layers 6 and 7	8535, 8536, 8543, 8549	Throughout the roof field	20% - 25% chrysotile

The following materials were found to be asbestos-containing.

NV5

Material	Sample No.	Material Location	Asbestos Content
		Building C	
White/black roof mastic	8056, 8057	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	2% -3% chrysotile
Rolled on roof core Layers 2,3,5,6,7	8059, 8060, 8063, 8064, 8066, 8069, 8074	Throughout the roof field and patio	<1% chrysotile – 50% chrysotile
		Building D	
White/black roof mastic	8076	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	3% chrysotile
Rolled on roof core Layers 1,2,5,7	8078, 8079, 8089, 8094	Throughout the roof field	<1% - 30% chrysotile
		Building E	
White and black roof mastic	8103	At all penetrations, pads, perimeter of the parapet wall, on flashing, and on conduit and pipe	3% chrysotile
Rolled on roof core Layers 4 and 6	8123, 8125	Throughout roof field on both levels	25% chrysotile
		Building F	
White and black roof mastic	8129, 8130	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	3% - 4% chrysotile
Rolled on roof core Layers 4,5,6,7	8138, 8139, 8145, 8146, 8153	Throughout roof field	30% chrysotile
		Sheds	
Rolled on roof core Layer 2	8614, 8616	Throughout roof field	3% - 5% chrysotile

The results for all other materials sampled were reported as "none detected," based on the limitations of the analytical method. Please refer to the Material Inventory (Appendix A) for a complete listing of materials sampled, locations, and material conditions.

If any materials are found to contain more than one percent asbestos by weight as determined by the PLM method of analysis, the EPA mandates that the material(s) be treated as ACM, subject to regulation under 40 CFR 61.



For the ACM identified in this report, dry sawing, sanding, or drilling should be avoided. Additional suspect materials may be exposed during demolition and/or renovation activities; such materials should be sampled and analyzed prior to further disturbance.

5.2 **LEAD**

Lead-based paint, according to the State of California and the USEPA is define as paint or other surface coating with lead content equal to or greater than 5,000 parts per million (ppm) by paint chip analysis. For occupational exposure, Cal/OSHA requires following a more stringent threshold wherein any detectable concentration of lead should be considered in worker protection.

The following are results of painted surfaces with any detectable levels of lead in paint below 5,000 ppm that were determined by paint chip sampling. When disturbed for construction purposes these surfaces are subjected to Cal/OSHA exposure assessment requirements set forth in *Title 8 CCR*, *Section* 1532.1(*d*). This regulation requires initial employee exposure monitoring to evaluate work exposure during work that disturbs paint with any detectable level of lead. If airborne lead levels are above the established Cal/OSHA action limit or permissible exposure limit, additional monitoring and respiratory protection are required.

Component	Sample No.	Substrate	Paint Color	Material Location	Results (ppm)
		Bi	uilding B		
Flashing	5166	Metal	Beige/white	Perimeter of building and visual barriers	150
		Bi	uilding D		
Visual barrier	4686	Wood	Beige/white	Inner and outer walls of visual barrier	97
		B	uilding E		
Flashing	4686	Metal	Biege/white	Perimeter of building and visual barriers	190

6.0 CONCLUSION AND RECOMMENDATIONS

6.1 **ASBESTOS**

The SCAQMD requires that all asbestos materials be removed prior to any renovation or demolition activities that may impact the material.

NV5

ACM removal shall be completed by a licensed asbestos abatement contractor utilizing isolation control methods and disposed of properly. Workers handling ACM shall be asbestos trained and shall wear the appropriate personal protective equipment.

An investigation below soil grade is outside the scope of this project, and additional material such as asbestos-cement pipes, electrical wiring insulation, or other materials may subsequently be discovered during site work.

Materials not clearly identified in this report should be properly sampled and characterized prior to disturbance.

6.2 **LEAD**

All construction work where an employee may be occupationally exposed to lead must comply with Cal/OSHA requirements set forth in 8 CCR 1532.1. This regulation requires initial employee exposure monitoring to evaluate worker exposure during work that disturbs lead-containing materials (lead present in detectable levels). NV5 suggests that engineering controls, respiratory protection and personal protective equipment be employed at the start of any project that could disturb LBP.

Waste generated during removal or demolition of LBP components must be properly segregated into separate waste streams. Each waste stream should be randomly sampled and each sample analyzed for lead by the California Waste Extraction Test for comparison to the Total Threshold Limit Concentration (TTLC), and Soluble Threshold Limit Concentration (STLC) and by Toxicity Characteristic Leaching Procedure (TCLP) as required, to determine the final disposition of the waste.

Workers who disturb surfaces with lead-containing paint are subject to regulation under *Title 8 CCR*, *Section 1532.1 (d)*. These requirements include awareness training, monitoring to determine worker exposure. This regulation requires initial and on-going (if necessary) employee exposure monitoring to evaluate lead work exposure that disturbs paint with any detectable level of lead. NV5 suggests that engineering controls, respiratory protection and personal protective equipment be employed at the start of any project that disturbs painted surfaces.

7.0 ASSUMPTIONS AND LIMITATIONS

This report was prepared exclusively for use by Rancho Santiago Community College District and may not be relied upon by any other person or entity without NV5's express written permission. The information, conclusions and recommendations described in this report apply to conditions existing at certain locations when services were performed and are intended only for the specific purposes, locations, time frames and project parameters indicated. NV5 cannot be responsible for the impact of any changes in environmental standards, practices, or regulations after performance of services.

In performing our professional services, we have applied present engineering and scientific judgment and used a level of effort consistent with the current standard of practice for similar types of studies.

As applicable, NV5 has relied in good faith upon representations and information furnished by individuals with respect to operations and existing property conditions, to the extent that they have not been contradicted by data obtained from other sources. Accordingly, NV5 accepts no



responsibility for any deficiencies, omissions, misrepresentations, or fraudulent acts of persons interviewed.

NV5 will not accept any liability for loss, injury claim, or damage arising directly or indirectly from any use or reliance on this report. NV5 makes no warranty, expressed or implied.

This report is issued with the understanding that the client, the property owner, or its representative is responsible for ensuring that the information, conclusions, and recommendations contained herein are brought to the attention of the appropriate regulatory agencies, as required.

Material quantities are in some cases listed within this document. These quantities are not intended to be used for removal bidding purposes. Nor is this document intended as a contract manual. Work methods and sequence, coordination of participants, applicable codes, engineering controls, required submittals and notifications should in all cases be addressed in a separate and independent bidding and contract document.

If you have any questions, please do not hesitate to contact the undersigned at (562) 495-5777. We appreciate the opportunity to be of service to Rancho Santiago Community College District.

8.0 SIGNATORY

Respectfully submitted by:

NV5

Eric J. Fleming, Project Manager Certified Asbestos Consultant Cal/OSHA Cert. #00-2186 Lead Inspector/Assessor CDPH Cert. #LRC-00003454

Reviewed by:

NV5

Christine Jordan

Project Manager, Building Sciences Cal/OSHA Cert. #92-0215 Lead Inspector/Assessor CDPH Cert. #LRC-00002523

N|V|5

APPENDIX A

Material Inventory

NV5

Asbestos

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building A

Sample No. Material Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage White and black roof 8550 5% chrysotile At all penetrations, 200 SF Southwest corner of No No pads, perimeter of the mastic southwest vent parapet wall, and on conduit and pipe 8551 5% chrysotile At all penetrations, White and black roof Northeast HVAC at 200 SF No No pads, perimeter of the mastic southwest corner parapet wall, and on conduit and pipe White and black roof 8552 5% chrysotile Center south wall of At all penetrations, 200 SF No No pads, perimeter of the mastic barrier area parapet wall, and on conduit and pipe 10' northwest of visual Patching throughout the Black roof mastic 8553 None detected 20 SF No No barrier roof field Patching throughout the Black roof mastic 8554 None detected Center south wall of barrier 20 SF No No roof field area Patching throughout the 8555 Center west side of barrier 20 SF Black roof mastic None detected No No roof field area Throughout the roof field Rolled on roof core -8556 None detected Center west wall 8.500 SF No No Laver 1 Rolled on roof core -Throughout the roof field 8557 None detected 8.500 SF Center west wall No No Laver 2 Rolled on roof core -8558 None detected Center west wall Throughout the roof field 8.500 SF No No Laver 3 Rolled on roof core -Throughout the roof field 8559 8,500 SF None detected Center west wall No No Laver 4 Rolled on roof core -Throughout the roof field 8560 None detected Center 8.500 SF No No Laver 1 Throughout the roof field Rolled on roof core -8561 None detected Center 8.500 SF No No Layer 2

Page 1 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building A

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Rolled on roof core -	8562	None detected	Center	Throughout the roof field	8,500 SF	No	No
Layer 3							
Rolled on roof core -	8563	None detected	Center	Throughout the roof field	8,500 SF	No	No
Layer 4							
Rolled on roof core -	8564	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 1			corner				
Rolled on roof core -	8565	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 2			corner				
Rolled on roof core -	8566	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 3			corner				
Rolled on roof core -	8567	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 4			corner				
Rolled on roof core -	8568	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 5			corner				
Rolled on roof core -	8569	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 6			corner				
Rolled on roof core -	8570	None detected	15' opposite the northeast	Throughout the roof field	8,500 SF	No	No
Layer 7			corner				

Page 2 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building B

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage White/black roof 8527 3% chrysotile 4' south of the northeast At all penetrations, 100 SF No No pads, perimeter of the mastic corner on parapet parapet wall, and on conduit and pipe 8528 White/black roof None detected Center north corner of At all penetrations, 100 SF No No pads, perimeter of the mastic access hatch parapet wall, and on conduit and pipe White/black roof 8529 3% chrysotile Barrier area center west At all penetrations, 100 SF No No wall pads, perimeter of the mastic parapet wall, and on conduit and pipe 10' west of the center east Rolled on roof core -8530 None detected Throughout the roof field 5,500 SF No No Layer 1 wall Rolled on roof core -8531 None detected 10' west of the center east Throughout the roof field 5,500 SF No No Laver 2 wall Rolled on roof core -Throughout the roof field 10' west of the center east 8532 None detected 5,500 SF No No Laver 3 wall Throughout the roof field Rolled on roof core -8533 None detected 10' west of the center east 5,500 SF No No Laver 4 wall Rolled on roof core -10' west of the center east Throughout the roof field 8534 None detected 5.500 SF No No Laver 5 wall Rolled on roof core -10' west of the center east Throughout the roof 8535 25% chrysotile 5,500 SF No No Laver 6 wall field 10' west of the center east Throughout the roof Rolled on roof core -8536 25% chrysotile 5,500 SF No No Laver 7 wall field Rolled on roof core -10' opposite the southwest Throughout the roof field 8537 None detected 5.500 SF No No Laver 1 corner Throughout the roof field Rolled on roof core -10' opposite the southwest 8538 None detected 5.500 SF No No Layer 2 corner

Page 3 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building B

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Rolled on roof core -	8539	None detected	10' opposite the southwest	Throughout the roof field	5,500 SF	No	No
Layer 3			corner				
Rolled on roof core -	8540	None detected	10' opposite the southwest	Throughout the roof field	5,500 SF	No	No
Layer 4			corner				
Rolled on roof core -	8541	None detected	10' opposite the southwest	Throughout the roof field	5,500 SF	No	No
Layer 5			corner				
Rolled on roof core -	8542	None detected	10' opposite the southwest	Throughout the roof field	5,500 SF	No	No
Layer 6			corner				
Rolled on roof core -	8543	25% chrysotile	10' opposite the	Throughout the roof	5,500 SF	No	No
Layer 7			southwest corner	field			
Rolled on roof core -	8544	None detected	Center	Throughout the roof field	5,500 SF	No	No
Layer 1							
Rolled on roof core -	8545	None detected	Center	Throughout the roof field	5,500 SF	No	No
Layer 2							
Rolled on roof core -	8546	None detected	Center	Throughout the roof field	5,500 SF	No	No
Layer 3							
Rolled on roof core -	8547	None detected	Center	Throughout the roof field	5,500 SF	No	No
Layer 4							
Rolled on roof core -	8548	None detected	Center	Throughout the roof field	5,500 SF	No	No
Layer 5							
Rolled on roof core -	8549	20% chrysotile	Center	Throughout the roof	5,500 SF	No	No
Layer 6				field			

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building C

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage White/black roof 8055 At all penetrations, None detected Southeast corner of 50 SF No No center south HVAC pads, perimeter of the mastic parapet wall, and on conduit and pipe 8056 2% chrysotile White/black roof Northwest corner of At all penetrations, 50 SF No No pads, perimeter of the center north HVAC mastic parapet wall, and on conduit and pipe White/black roof 8057 3% chrysotile Southwest corner of At all penetrations, 50 SF No No pads, perimeter of the mastic access hatch parapet wall, and on conduit and pipe Rolled on roof core -8058 None detected Southeast corner Throughout the roof field 3,500 SF No No and patio Laver 1 Throughout the roof Rolled on roof core -2% chrysotile 8059 Southeast corner 3,500 SF No No Laver 2 field and patio Rolled on roof core -Throughout the roof 8060 2% chrysotile Southeast corner 3.500 SF No No Laver 3 field and patio Throughout the roof field Rolled on roof core -8061 None detected Southeast corner 3.500 SF No No Laver 4 and patio Throughout the roof field Rolled on roof core -8062 None detected 3.500 SF Southeast corner No No Laver 5 and patio Rolled on roof core -Throughout the roof 8063 50% chrysotile Southeast corner 3,500 SF No No Laver 6 field and patio Throughout the roof Rolled on roof core -8064 50% chrysotile Southeast corner 3,500 SF No No Laver 7 field and patio Rolled on roof core -Throughout the roof field 8065 None detected 10' south of center north 3.500 SF No No wall and patio Laver 1 Throughout the roof Rolled on roof core -8066 <1% chrysotile 10' south of center north 3,500 SF No No Laver 2 wall field and patio

Page 5 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building C

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Rolled on roof core -	8067	None detected	10' south of center north	Throughout the roof field	3,500 SF	No	No
Layer 3			wall	and patio			
Rolled on roof core -	8068	None detected	10' south of center north	Throughout the roof field	3,500 SF	No	No
Layer 4			wall	and patio			
Rolled on roof core -	8069	50% chrysotile	10' south of center north	Throughout the roof	3,500 SF	No	No
Layer 5		-	wall	field and patio			
Rolled on roof core -	8070	None detected	10' south of center west wall	Throughout the roof field	3,500 SF	No	No
Layer 1				and patio			
Rolled on roof core -	8071	None detected	10' south of center west wall	Throughout the roof field	3,500 SF	No	No
Layer 2				and patio			
Rolled on roof core -	8072	None detected	10' south of center west wall	Throughout the roof field	3,500 SF	No	No
Layer 3				and patio			
Rolled on roof core -	8073	None detected	10' south of center west wall	Throughout the roof field	3,500 SF	No	No
Layer 4				and patio			
Rolled on roof core -	8074	30% chrysotile	10' south of center west	Throughout the roof	3,500 SF	No	No
Layer 5			wall	field and patio			

Page 6 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building C110

Material Sample No. **Asbestos Content Material Location** Friable Sample Location Approx. Qty. Damage Roof core 8619 None detected Center Throughout roof field 1,500 SF No No None detected Throughout roof field 1,500 SF No Roof core 8620 North center No Roof core 8621 Throughout roof field 1,500 SF No No None detected Southeast corner Black and white mastic 8622 None detected At penetrations and pads 25 SF Northwest corner No No Black and white mastic 8623 At penetrations and pads 25 SF No No None detected Southwest corner Black and white mastic 8624 None detected Center south At penetrations and pads 25 SF No No

Page 7 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center C111

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
White and black mastic	8601	None detected	North center	At all penetrations, pads,	25 SF	No	No
				and on conduit and pipe			
White and black mastic	8602	None detected	West center	At all penetrations, pads,	25 SF	No	No
				and on conduit and pipe			
White and black mastic	8603	None detected	Center	At all penetrations, pads,	25 SF	No	No
				and on conduit and pipe			
Rolled on roof core -	8604	None detected	Southeast corner	Throughout the roof field	1,500 SF	No	No
Layer 1							
Rolled on roof core -	8605	None detected	Southeast corner	Throughout the roof field	1,500 SF	No	No
Layer 2							
Rolled on roof core -	8606	None detected	Southeast corner	Throughout the roof field	1,500 SF	No	No
Layer 3							
Rolled on roof core -	8607	None detected	Center	Throughout the roof field	1,500 SF	No	No
Layer 1							
Rolled on roof core -	8608	None detected	Center	Throughout the roof field	1,500 SF	No	No
Layer 2							
Rolled on roof core -	8609	None detected	Center	Throughout the roof field	1,500 SF	No	No
Layer 3							
Rolled on roof core -	8610	None detected	North center	Throughout the roof field	1,500 SF	No	No
Layer 1							
Rolled on roof core -	8611	None detected	North center	Throughout the roof field	1,500 SF	No	No
Layer 2							
Rolled on roof core -	8612	None detected	North center	Throughout the roof field	1,500 SF	No	No
Layer 3							

Page 8 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building D

Sample No. Approx. Qty. Material Asbestos Content Sample Location Material Location Friable Damage White/black roof mastic 8075 None detected Northwest corner of visual At all penetrations, pads, 50 SF No No perimeter of the parapet barrier area wall, and on conduit and pipe White/black roof 8076 3% chrysotile Center south penetration At all penetrations, 50 SF No No pads, perimeter of the mastic parapet wall, and on conduit and pipe 8077 At all penetrations, pads, White/black roof mastic None detected Northwest corner of access 50 SF No No perimeter of the parapet hatch wall, and on conduit and pipe <1% chrysotile Throughout the roof Rolled on roof core -8078 Center of roof 2.500 SF No No Laver 1 field Throughout the roof Rolled on roof core -8079 <1% chrysotile Center of roof 2,500 SF No No field Laver 2 Rolled on roof core -Throughout the roof field 2,500 SF 8080 None detected Center of roof No No Laver 3 Rolled on roof core -Throughout the roof field 8081 None detected Center of roof 2,500 SF No No Laver 4 Rolled on roof core -Throughout the roof field 2.500 SF 8082 None detected Center of roof No No Laver 5 Rolled on roof core -8083 None detected Center of the west wall Throughout the roof field 2.500 SF No No Layer 1 Rolled on roof core -Throughout the roof field 8084 None detected Center of the west wall 2.500 SF No No Laver 2 Rolled on roof core -Throughout the roof field 8085 None detected Center of the west wall 2.500 SF No No Laver 3 Rolled on roof core -Center of the west wall Throughout the roof field 8086 None detected 2.500 SF No No Laver 4

Page 9 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building D

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Rolled on roof core -	8087	None detected	Center of the west wall	Throughout the roof field	2,500 SF	No	No
Layer 5							
Rolled on roof core -	8088	None detected	Center of the west wall	Throughout the roof field	2,500 SF	No	No
Layer 6							
Rolled on roof core -	8089	30% chrysotile	Center of the west wall	Throughout the roof	2,500 SF	No	No
Layer 7		-		field			
Rolled on roof core -	8090	None detected	5' southwest of the access	Throughout the roof field	2,500 SF	No	No
Layer 1			hatch				
Rolled on roof core -	8091	None detected	5' southwest of the access	Throughout the roof field	2,500 SF	No	No
Layer 2			hatch	_			
Rolled on roof core -	8092	None detected	5' southwest of the access	Throughout the roof field	2,500 SF	No	No
Layer 3			hatch	_			
Rolled on roof core -	8093	None detected	5' southwest of the access	Throughout the roof field	2,500 SF	No	No
Layer 4			hatch	-			
Rolled on roof core -	8094	30% chrysotile	5' southwest of the access	Throughout the roof	2,500 SF	No	No
Layer 5		-	hatch	field			

Page 10 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center D106 &107

Material Sample No. Asbestos Content Material Location Approx. Qty. Friable Sample Location Damage Northeast corner of D107 Throughout roof field Roof core 8571 None detected 1,800 SF No No Roof core Throughout roof field 1,800 SF 8572 None detected Southwest corner of D106 No No Roof core 8573 None detected Northwest corner of D106 Throughout roof field 1,800 SF No No White and black mastic Center of D106 At penetrations and pads 8574 None detected 25 SF No No White and black mastic 8575 None detected Southwest corner of D106 At penetrations and pads 25 SF No No White and black mastic 8576 At penetrations and pads 25 SF Northwest corner of D107 None detected No No

Page 11 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center D108

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage Throughout roof field 1,200 SF Roof core 8577 None detected Center south No No Roof core Throughout roof field 1,200 SF 8578 None detected Center west No No 8579 Roof core None detected Southeast corner Throughout roof field 1,200 SF No No White and black mastic 8580 At penetrations and pads 15 SF None detected Center west No No White and black mastic 8581 None detected Southwest corner At penetrations and pads 15 SF No No White and black mastic 8582 None detected At penetrations and pads 15 SF No Center No

Page 12 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center D109

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage Throughout roof field 1,200 SF Roof core 8583 None detected Center north No No Roof core Throughout roof field 1,200 SF 8584 None detected Southwest corner No No 8585 Roof core None detected Center Throughout roof field 1,200 SF No No White and black mastic 8586 At penetrations and pads 15 SF None detected West center No No White and black mastic 8587 None detected East center At penetrations and pads 15 SF No No White and black mastic 8588 None detected At penetrations and pads 15 SF No Northeast corner No

Page 13 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building D110

Material Sample No. Asbestos Content Material Location Approx. Qty. Friable Sample Location Damage 8095 Throughout roof field 1,200 SF Roof core None detected Center north No No Roof core Throughout roof field 1,200 SF 8096 None detected Center east No No 8097 Roof core None detected Southwest corner Throughout roof field 1,200 SF No No White and black mastic 8098 At penetrations and pads 15 SF None detected Center north No No White and black mastic 8099 None detected Center west At penetrations and pads 15 SF No No White and black mastic 8100 None detected At penetrations and pads 15 SF No Southeast corner No

Page 14 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center D111

Material Sample No. Asbestos Content Material Location Approx. Qty. Friable **Sample Location** Damage 8595 Throughout roof field 1,200 SF Roof core None detected Center south No No Roof core Throughout roof field 1,200 SF 8596 None detected Northwest corner No No 8597 Roof core None detected Throughout roof field 1,200 SF No No Northeast corner White and black mastic 8598 At penetrations and pads 15 SF None detected Center south No No White and black mastic 8599 None detected Center At penetrations and pads 15 SF No No White and black mastic 8600 None detected At penetrations and pads 15 SF No Southeast corner No

Page 15 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center D112

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage 8589 Throughout roof field 1,200 SF Roof core None detected Center north No No Roof core Center south Throughout roof field 1,200 SF 8590 None detected No No 8591 Roof core None detected Throughout roof field 1,200 SF No No Center White and black mastic 8592 At penetrations and pads 15 SF None detected Northeast corner No No White and black mastic 8593 None detected Center east At penetrations and pads 15 SF No No White and black mastic 8594 None detected At penetrations and pads 15 SF No Center south No

Page 16 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building E

Sample No. **Material Location** Material Asbestos Content Sample Location Approx. Qty. Friable Damage At all penetrations, pads, White and black roof 8101 None detected Center visual barrier area. 200 SF No No mastic northeast corner perimeter of the parapet wall, on flashing, and on conduit and pipe At all penetrations, pads, White and black roof 8102 200 SF No No None detected Southwest corner of access hatch perimeter of the parapet mastic wall, on flashing, and on conduit and pipe White and black roof 8103 3% chrysotile West visual barrier area. At all penetrations, 200 SF No No pads, perimeter of the mastic northwest corner parapet wall, on flashing, and on conduit and pipe Patching in west visual 8104 Southwest corner of 20 SF Black roof mastic None detected No No northwest HVAC unit barrier area Patching in west visual Black roof mastic 8105 None detected Center west wall 20 SF No No barrier area 8106 Patching in west visual 20 SF Black roof mastic None detected Southwest corner of No No southeast HVAC unit barrier area 15' opposite the southwest Throughout roof field on 9.000 SF Rolled on roof core -8107 None detected No No both levels Laver 1 corner Rolled on roof core -15' opposite the southwest Throughout roof field on 8108 9.000 SF No None detected No Laver 2 both levels corner 15' opposite the southwest Throughout roof field on Rolled on roof core -8109 9,000 SF None detected No No Layer 3 corner both levels 15' opposite the southwest Rolled on roof core -Throughout roof field on 8110 None detected 9,000 SF No No Laver 4 both levels corner Rolled on roof core -15' opposite the southwest Throughout roof field on 9,000 SF 8111 None detected No No Layer 5 corner both levels

Page 17 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building E

Sample No. Material Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage Throughout roof field on 15' opposite the southwest Rolled on roof core -8112 None detected 9,000 SF No No both levels Laver 6 corner Rolled on roof core -15' opposite the southwest Throughout roof field on 8113 9.000 SF None detected No No both levels Laver 7 corner Rolled on roof core -Center of upper roof Throughout roof field on 8114 9,000 SF None detected No No both levels Layer 1 Rolled on roof core -Throughout roof field on 8115 Center of upper roof 9,000 SF None detected No No Laver 2 both levels Rolled on roof core -Center of upper roof Throughout roof field on 8116 None detected 9,000 SF No No both levels Layer 3 Rolled on roof core -Throughout roof field on 8117 Center of upper roof 9,000 SF None detected No No Laver 4 both levels Rolled on roof core -Center of upper roof Throughout roof field on 8118 None detected 9,000 SF No No both levels Layer 5 Throughout roof field on Rolled on roof core -8119 None detected Center of upper roof 9,000 SF No No Laver 6 both levels Rolled on roof core -10' opposite the northeast Throughout roof field on 9,000 SF 8120 None detected No No both levels Laver 1 corner 10' opposite the northeast Throughout roof field on 9,000 SF Rolled on roof core -8121 None detected No No Laver 2 corner both levels Rolled on roof core -10' opposite the northeast Throughout roof field on 9.000 SF 8122 None detected No No both levels Laver 3 corner Rolled on roof core -8123 25% chrysotile 10' opposite the northeast Throughout roof field 9,000 SF No No on both levels Laver 4 corner 10' opposite the northeast Rolled on roof core -Throughout roof field on 8124 None detected 9,000 SF No No both levels Laver 5 corner Rolled on roof core -10' opposite the northeast Throughout roof field 8125 25% chrysotile 9,000 SF No No Layer 6 corner on both levels

Page 18 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building F

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage White and black roof 8129 4% chrysotile At all penetrations, 200 SF West visual barrier area. No No pads, perimeter of the mastic northeast corner parapet wall, and on conduit and pipe 8130 3% chrysotile Southeast penetration White and black roof At all penetrations, 200 SF No No pads, perimeter of the mastic parapet wall, and on conduit and pipe White and black roof 8131 None detected East visual barrier area. At all penetrations, 200 SF No No pads, perimeter of the mastic northwest corner of the parapet wall, and on southwest HVAC unit conduit and pipe Patching throughout the Black roof mastic 8132 None detected West barrier area, center 50 SF No No south wall roof field West barrier area, 5' north Patching throughout the Black roof mastic 8133 50 SF None detected No No of the southwest corner roof field Patching throughout the Black roof mastic 8134 None detected East barrier area, at center 50 SF No No north of southeast HVAC roof field Rolled on roof core -8135 None detected 10' opposite the southeast Throughout roof field 6.500 SF No No Laver 1 corner 10' opposite the southeast Rolled on roof core -8136 None detected Throughout roof field 6.500 SF No No Laver 2 corner 10' opposite the southeast Rolled on roof core -8137 None detected Throughout roof field 6.500 SF No No Laver 3 corner 10' opposite the southeast Throughout roof field Rolled on roof core -8138 30% chrysotile 6,500 SF No No Laver 4 corner Rolled on roof core -8139 30% chrysotile 10' opposite the southeast Throughout roof field 6,500 SF No No Laver 5 corner Rolled on roof core -Throughout roof field 8140 None detected Center 6.500 SF No No Laver 1

Page 19 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building F

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Rolled on roof core - Layer 2	8141	None detected	Center	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 3	8142	None detected	Center	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 4	8143	None detected	Center	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 5	8144	None detected	Center	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 6	8145	30% chrysotile	Center	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 7	8146	30% chrysotile	Center	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 1	8147	None detected	20' opposite the northwest corner	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 2	8148	None detected	20' opposite the northwest corner	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 3	8149	None detected	20' opposite the northwest corner	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 4	8150	None detected	20' opposite the northwest corner	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 5	8151	None detected	20' opposite the northwest corner	Throughout roof field	6,500 SF	No	No
Rolled on roof core - Layer 6	8152	None detected	20' opposite the northwest corner	Throughout roof field	6,500 SF	No	No
Rolled on roof core -	8153	30% chrysotile	20' opposite the northwest	Throughout roof field	6,500 SF	No	No
Layer /			corner				

Page 20 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building G

Material Sample No. Asbestos Content Sample Location Material Location Approx. Qty. Friable Damage 8126 None detected Center Throughout roof field 3,800 SF Roof core No No 15' opposite the southwest Roof core Throughout roof field 3,800 SF No 8127 None detected No corner Roof core 8128 None detected 10' opposite the northeast Throughout roof field 3,800 SF No No corner

Page 21 of 22

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Sheds
RSCC-24-12223

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Rolled on roof core -	8613	None detected	Northwest corner	Throughout roof field	100 SF	No	No
Layer 1							
Rolled on roof core -	8614	5% chrysotile	Northwest corner	Throughout roof field	100 SF	No	No
Layer 2							
Rolled on roof core -	8615	None detected	Center north	Throughout roof field	100 SF	No	No
Layer 1							
Rolled on roof core -	8616	3% chrysotile	Center north	Throughout roof field	100 SF	No	No
Layer 2				_			
Rolled on roof core -	8617	None detected	Southeast corner	Throughout roof field	100 SF	No	No
Layer 1							
Rolled on roof core -	8618	None detected	Southeast corner	Throughout roof field	100 SF	No	No
Layer 2							

Page 22 of 22
NV5

Lead

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building A

Approx. Component Sample No. Substrate Paint Color **Sample Location** Material Location **Results (PPM)** Damage Damage Qty. Flashing 5169 Metal Beige/white Center north wall Perimeter of building and <49 No NA visual barriers 5170 Visual barrier Wood Beige/white Center north wall Inner and outer walls of <49 No NA visual barrier Pipe/conduit 5171 Metal White 20' east of the center Throughout roof <47 No NA west wall

Page 1 of 16

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building B

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	5166	Metal	Beige/white	Center west wall of	Perimeter of building and	150	No	NA
				barrier area	visual barriers			
Visual barrier	5167	Wood	Beige/white	Northeast corner	Inner and outer walls of	<48	No	NA
					visual barrier			
Pipe/conduit	5168	Metal	White	Center of barrier area	Throughout roof	<50	No	NA

Page 2 of 16

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building C

Approx. Component Sample No. Substrate Paint Color **Sample Location Material Location Results (PPM)** Damage Damage Qty. Flashing 4680 Metal Beige/white Center north wall Perimeter of building and <49 No NA visual barriers Visual barrier 4681 Wood Beige/white Northwest corner Inner and outer walls of <56 No NA visual barrier Visual barrier frame 4682 Metal Beige Southwest corner Throughout visual barrier <49 NA No Pipe/conduit 4683 White Center of roof Throughout roof <46 NA Metal No

Page 3 of 16

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg C110

Page 4 of 16

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	5190	Metal	Brown	5' east of the southwest	Perimeter of building	<94	No	NA
				corner				
Gutter	5191	Metal	Brown	10' north of the	Perimeter of building	<130	No	NA
				southwest corner				

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg C111

Page 5 of 16

Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Approx. Damage Qty.
Flashing	5186	Metal	Brown	West center	Perimeter of building	<65	No	NA
Gutter	5187	Metal	Brown	West center	Perimeter of building	<53	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:Centennial Education CenterPROJECT NAME:RSCC-24-12223

Page 6 of 16

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	4685	Metal	Beige/white	Entrance to visual barrier	Perimeter of building and	<48	No	NA
				area	visual barriers			
Visual barrier	4686	Wood	Beige/white	Northeast corner of	Inner and outer walls of	97	No	NA
				visual barrier	visual barrier			
Pipe/conduit	4687	Metal	White	Center of visual barrier	Throughout roof	<48	No	NA
				area				

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg D106&107

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	5172	Metal	Beige	Southeast corner of D106	Perimeter of building	<50	No	NA
Pipe/conduit	5173	Metal	White	Center west wall of D107	Throughout roof	<49	No	NA
Gutter	5174	Metal	Brown	Southeast corner of D106	Perimeter of building	<140	No	NA
HVAC duct/support	5175	Metal	White	Center west wall of D107	At HVAC unit	<49	No	NA

Page 7 of 16

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg D108

Page 8 of 16

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	5176	Metal	Beige	Southeast corner	Perimeter of building	<49	No	NA
Pipe/conduit	5177	Metal	White	Center south wall	Throughout roof	<220	No	NA
Gutter	5178	Metal	Brown	Southeast corner	Perimeter of building	<49	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg D109

Page 9 of 16

Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Approx. Damage Qty.
Flashing	5179	Metal	Beige	Center south	Perimeter of building	<49	No	NA
Gutter	5180	Metal	Brown	Center south	Perimeter of building	<210	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg D110

Page 10 of 16

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	4684	Metal	Beige	Center south wall	Perimeter of building	<49	No	NA
Pipe/conduit	4685	Metal	White	Center south wall	Throughout roof	<47	No	NA
Gutter	4686	Metal	Brown	Northeast corner	Perimeter of building	<48	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg D111

Page 11 of 16

Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Approx. Damage Qty.
Flashing	5184	Metal	Beige	Northeast corner	Perimeter of building	<48	No	NA
Gutter	5185	Metal	Brown	Northeast corner	Perimeter of building	<47	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg D112

Page 12 of 16

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	5181	Metal	Beige	Southeast corner	Perimeter of building	<49	No	NA
Pipe/conduit	5182	Metal	White	Northeast corner	Throughout roof	<48	No	NA
Gutter	5183	Metal	Brown	Southeast corner	Perimeter of building	<240	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Bldg E

Approx. Component Sample No. Substrate Paint Color **Sample Location Material Location Results (PPM)** Damage Damage Qty. Flashing 4686 Metal Beige/white Southeast corner of Perimeter of building and 190 No NA upper roof visual barriers Beige/white <48 Visual barrier 4687 Wood Southeast corner of Inner and outer walls of No NA north visual barrier area visual barrier White <47 Pipe/conduit 4688 Metal Center of west barrier Throughout roof No NA area

Page 13 of 16

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building G

Page 14 of 16

Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Approx. Damage Qty.
Flashing	4689	Metal	Beige	Center west wall	Perimeter	<220	No	NA

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Building F

Approx. Component Sample No. Substrate Paint Color **Sample Location Material Location Results (PPM)** Damage Damage Qty. Flashing 4690 Metal Beige/white East barrier area, Perimeter of building and <49 No NA northwest corner visual barriers Beige/white Visual barrier 4691 Wood West barrier area, Inner and outer walls of <47 No NA center west wall visual barrier White Pipe/conduit 4692 Metal West barrier area, Throughout roof <46 No NA center north side of southeast HVAC unit

Page 15 of 16

CLIENT:Rancho Santiago Community College DistrictPROJECT NO:RSCC-24-12223PROJECT NAME:Centennial Education Center Sheds

Page 16 of 16

								Approx.
Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Damage Qty.
Flashing	5188	Metal	Brown	Center south	Perimeter	<71	No	NA
Fascia	5189	Wood	Brown	Center south	Perimeter	<49	No	NA

N | V | 5

APPENDIX B

Laboratory Analytical Report

NIV 5

Asbestos



Alta Environme	ntal	Project N	umber	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project N	ame	Building A
Long Beach, C	A 90807	Location		Santa Ana, CA
Attn.: Eric Flemi	ing	PO Numb	er	
Report Number	2458476	WO Numi)er	
Date Received	05/06/2024	Date Sam	pled	05/04/2024
Date Analyzed	05/07/2024	Sampled	Ву	
Date Reported	05/07/2024	Total San	nples	21

sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test I	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458476-001						
8550	Roof mastic, White/Silver/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix Binder/Filler	10% 5% 65% 15%	Chrysotile	5%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	95.0%	Total %Asbestos:	5.0%
2458476-002						
8551	Roof mastic, White/Silver/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix Binder/Filler	10% 5% 65% 15%	Chrysotile	5%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	95.0%	Total %Asbestos:	5.0%
2458476-003 8552	Roof mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	5% 80% 10%	Chrysotile	5%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	95.0%	Total %Asbestos:	5.0%
2458476-004 8553	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 80%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458476-005 8554	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 80%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458476-006 8555	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 80%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building A
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458476	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	21

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458476-007								
8556	Rolled on roof core - Layer 1,	LAYER 1	Synthetic Fiber Fibrous Glass	25% 10%	None Detected			
	white/Silver/Diack, Non-homogeneous	5 100 %	Metallic Paint Bituminous Matrix Binder/Filler	10% 45% 10%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458476-008								
8557	Rolled on roof core - Layer 2,	LAYER 1	Fibrous Glass	20%	None Detected			
	Silver/Black, Non-homogeneous	100%	Metallic Paint Bituminous Matrix	5% 75%				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458476-009								
8558	Rolled on roof core - Layer 3, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 80%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458476-010								
8559	Rolled on roof core - Layer4,	LAYER 1	Cellulose Fiber	15%	None Detected			
	Black/Brown, Non-homogeneous	100%	Fibrous Glass Bituminous Matrix	10% 75%				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458476-011								
8560	Rolled on roof core - Layer 1, White/	LAYER 1	Fibrous Glass	10%	None Detected			
	Black, Non-nomogeneous	100%	Metallic Paint Bituminous Matrix Binder/Filler	10% 30% 50%				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458476-012								
8561	Rolled on roof core - Layer 2, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	30% 70%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	I	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	I	Project Name	Building A
Long Beach, C	A 90807	I	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	I	PO Number	
Report Number	2458476	١	WO Number	
Date Received	05/06/2024	I	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	5	Sampled By	
Date Reported	05/07/2024	-	Total Samples	21

Ysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report							
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458476-013								
8562	Rolled on roof core - Layer 2, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 80%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458476-014								
8563	Rolled on roof core - Layer 4, Gray, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 20% 65%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458476-015								
8564	Rolled on roof core - Layer 1, White/Silver/Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Metallic Paint Bituminous Matrix Binder/Filler	40% 10% 25% 25%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458476-016								
8565	Rolled on roof core - Layer 2, Silver/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix	40% 5% 55%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458476-017								
8566	Rolled on roof core - Layer 3,	LAYER 1	Fibrous Glass	30%	None Detected			
	Silver/Black, Non-homogeneous	100%	Metallic Paint Bituminous Matrix	5% 65%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458476-018								
8567	Rolled on roof core - Layer 4, Silver/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix	30% 5% 65%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building A
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458476	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	21

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test F	Report						
Laboratory ID	Laboratory ID Sample Location Layer No. Non-Asbestos Asbestos								
Sample No.	Description	Layer %	Components	(%)	Туре	(%)			
2458476-019									
8568	Rolled on roof core - Layer 5, Black,	LAYER 1	Fibrous Glass	10%	None Detected				
	Homogeneous	100%	Bituminous Matrix	90%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected			
2458476-020									
8569	Rolled on roof core - Layer 6, Gray,	LAYER 1	Fibrous Glass	20%	None Detected				
	Non-homogeneous	100%	Quartz/Gravel	30%					
			Bituminous Matrix/Filler	50%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected			
2458476-021									
8570	Rolled on roof core - Layer 7, Black,	LAYER 1	Cellulose Fiber	15%	None Detected				
	Homogeneous	100%	Fibrous Glass	<1%					
			Bituminous Matrix/Filler	85%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected			

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Atma &Tabatt Custma &Tabatt

R TESTING NVLAP Lab Code 500044-0

Approved Signatory Cristina E. Tabatt



CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No. 20	158476						
	CUSTOMER INF	ORMATIC	N	Turnaround	Time	Shippe	d By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., An	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off	Ø	Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877	_		Special In	structions:					
Email	eric.fleming@nv5	.com		Layered a	analysis on	drywall/j	oint com	pound		
			PROJECT	INFORMA	TION					
Project Name	Building A		TROOLOT	PO Numbe	r					
Project Number:	RSCC-24-12223			Work Orde	r No.:	3				
Location:	Santa Ana, CA	_		Sampled B	v:					
				-						
PL	_M	P	CM		MOLD	_		LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 7	400A	S T	pore Trap		Air		TILC	
PLM 400 Pt. Cou	(<0.25%)	w/ TWA		В	ulk Sample		Wine			
			_	5	Swab		Soil			
SAMPLE ID	SAMPLE T	/PE		LOCAT	ION		Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
8550	White and black ro	oof mastic		NA			5/4/2024	NA	NA	NA
8551	White and black re	of mastic		NA	4		5/4/2024	NA	NA	NA
8552	White and black re	of mastic		NA	Ą		5/4/2024	NA	NA	NA
8553	Black roof m	astic		NA	Ą		5/4/2024	NA	NA	NA
8554	Black roof m	astic		NA	Ą		5/4/2024	NA	NA	NA
8555	Black roof m	astic		NA	Ą		5/4/2024	NA	NA	NA
8556	Rolled on roof core	e - Layer 1		NA	Ą		5/4/2024	NA	NA	NA
8557	Rolled on roof core	e - Layer 2		NA	Ą		5/4/2024	NA	NA	NA
8558	Rolled on roof core	e - Layer 3		NA	4		5/4/2024	NA	NA	NA
8559	Rolled on roof core	- Layer 4		NA	A		5/4/2024	NA	NA	NA
Relinquished By:	61			Received B	by: A	m	/	. <u>Managan</u> a (1997)		
Printed Name	Eric Flomi	2		Printed Nar	me Jau	Kie Thy	11			
Date/Time:	5-5-24 1	for	1	Date/Time:	5/61	124 à	500			
Relinquished By:				Received E	sy:					
Printed Name				Printed Nar	me					
Date/Time:				Date/Time:					Lab Form	ns

Ver. 2016-06-27

CHAIN OF CUSTODY



Date/Time:

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

Company:	Alta Environmental/NV5		(Lab) Order No.	2458471	0	
Project Number:	RSCC-24-12223			- 12 - 1 - 1	~	
Project Name:						
SAMPLE ID	SAMPLE TYPE	LOCATION	Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
8560	Rolled on roof core - Layer	NA	5/4/2024	NA	NA	NA
8561	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA
8562	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA
8563	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA
8564	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA
8565	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA
8566	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA
8567	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA
8568	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA
8569	Rolled on roof core - Layer 6	NA	5/4/2024	NA	NA	NA
8570	Rolled on roof core - Layer 7	NA	5/4/2024	NA	NA	NA
Relinquished By:	41	Received By:	ano			
Printed Name	Eric Plania	Printed Name Jacki	etaya1			
Date/Time:	5-5-24 120	Date/Time: 5/6/3	24 0800			
Relinquished By:		Received By:				
Printed Name		Printed Name			Lab Form	15

Pagete/Tinof:



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building B
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458475	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	23

Ysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report							
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos) Type	(%)	
2458475-001 8527	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Bituminous Matrix/Filler Other Non-Fibrous Material	52% 45%	Chrysotile	3%	
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	97.0%	Total %Asbestos:	3.0%	
2458475-002 8528	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	5% 50% 45%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	
2458475-003 8529	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	10% 47% 40%	Chrysotile	3%	
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	97.0%	Total %Asbestos:	3.0%	
2458475-004 8530	Rolled on roof core - Layer 1, White/Black/Silver, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	25% 10% 45% 20%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	
2458475-005 8531	Rolled on roof core - Layer 2, Black/Silver, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	20% 75% 5%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	
2458475-006 8532	Rolled on roof core - Layer 3, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building B
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458475	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	23

sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report						
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)	
2458475-007							
8533	Rolled on roof core - Layer 4, Black, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Bituminous Matrix/Filler	45% 5% 50%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	
2458475-008							
8534	Rolled on roof core - Layer 5, White/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	10% 65% 25%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	
2458475-009							
8535	Rolled on roof core - Layer 6, Dk. Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	45% 30%	Chrysotile	25%	
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	75.0%	Total %Asbestos:	25.0%	
2458475-010							
8536	Rolled on roof core - Layer 7, Dk. Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	45% 30%	Chrysotile	25%	
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	75.0%	Total %Asbestos:	25.0%	
2458475-011							
8537	Rolled on roof core - Layer 1, White/Black/Silver, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Bituminous Matrix Other Non-Fibrous Material	35% 35% 30%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	
2458475-012							
8538	Rolled on roof core - Layer 2, Silver/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	30% 60% 10%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected	



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building B
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458475	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	23

/Sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report					
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458475-013						
8539	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458475-014						
8540	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	65% 35%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458475-015						
8541	Rolled on roof core - Layer 5,	LAYER 1	Fibrous Glass	10%	None Detected	
	White/Black, Non-homogeneous	100%	Bituminous Matrix/Filler Other Non-Fibrous Material	65% 25%		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458475-016						
8542	Rolled on roof core - Layer 6,	LAYER 1	Fibrous Glass	15%	None Detected	
	White/Black, Non-homogeneous	100%	Bituminous Matrix/Filler Other Non-Fibrous Material	55% 30%		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458475-017						
8543	Rolled on roof core - Layer 7, Black,	LAYER 1	Cellulose Fiber	55%	Chrysotile	25%
	Homogeneous	100%	Bituminous Matrix	20%		
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	75.0%	Total %Asbestos:	25.0%
2458475-018						
8544	Rolled on roof core - Layer 1,	LAYER 1	Synthetic Fiber	25% 10%	None Detected	
	white/Black/Sliver, Non-nomogeneous	100%	Bituminous Matrix/Filler Other Non-Fibrous Material	50% 15%		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building B
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458475	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	23

Sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test R	leport			
Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
2458475-019						
8545	Rolled on roof core - Layer 2, Black/Silver, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Materia	35% 50% I 15%	None Detected	
	Asbestos Present: No	Tota	I % Non-Asbestos:	100.0% '	Total %Asbestos:	No Asbestos Detected
2458475-020						
8546	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	I % Non-Asbestos:	100.0% '	Total %Asbestos:	No Asbestos Detected
2458475-021						
8547	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	75% 25%	None Detected	
	Asbestos Present: No	Tota	I % Non-Asbestos:	100.0% '	Total %Asbestos:	No Asbestos Detected
2458475-022						
8548	Rolled on roof core - Layer 5, White/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Materia	15% 60% al 25%	None Detected	
	Asbestos Present: No	Tota	I % Non-Asbestos:	100.0% '	Total %Asbestos:	No Asbestos Detected
2458475-023						
8549	Rolled on roof core - Layer 6, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	60% 20%	Chrysotile	20%
	Asbestos Present: Yes	Tota	I % Non-Asbestos:	80.0%	Total %Asbestos:	20.0%



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming

Report Number 2458475

 Date Received
 05/06/2024

 Date Analyzed
 05/07/2024

 Date Reported
 05/07/2024

Method of Analysis

Analyst -

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building B

05/04/2024

23

Santa Ana, CA

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report							
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	S	
Sample No.	Description	Layer %	Components	(%)	Туре	(%)	

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Fred Chappelear

Custma 2Tabatt

NVLAP Lab Code 500044-0

Approved Signatory Cristina E. Tabatt



ſ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

	CUSTOMER INF	ORMATIO	N	Turnaround	d Time	Shippe	d By	Repor	t Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special Ir	structions:					
Email	eric.fleming@nv5	.com		Layered	analysis on	n drywall/j	oint com	pound		
			PROJECT	INFORMA	TION					
Project Name:	Building B			PO Numbe	ər:					
Project Number:	RSCC-24-12223			Work Orde	er No.:					
Location:	Santa Ana, CA			Sampled E	By:					
PI	M	Р	СМ	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	1-82-020	NIOSH 74	400A 🗆	5	Spore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	400B 🗆	1 7	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		E	Bulk Sample		Wipe			
		(05		1.0004	Swab		Soil	Start Time	Aug	Volumo
SAMPLE ID	SAMPLE I	PE		LOCA	TION		Sampled	Stop Time	Flow Rate	
							Suppor	NA	NA	(=)
8527	White and black ro	of mastic		N	A		5/4/2024		NA	NA
8528	White and black ro	of mastic		Ν	A		5/4/2024	NA	NA	NA
8529	White and black ro	of mastic		N	A		5/4/2024	NA	NA	NA
8530	Rolled on roof core	e - Layer 1		N	A		5/4/2024	NA	NA	NA
8531	Rolled on roof core	e - Layer 2		N	A		5/4/2024	NA	NA	NA
8532	Rolled on roof core	e - Layer 3		N	A		5/4/2024	NA	NA	NA
8533	Rolled on roof core	e - Layer 4		N	A		5/4/2024	NA	NA	NA
8534	Rolled on roof core	e - Layer 5		N	A		5/4/2024	NA	NA	NA
8535	Rolled on roof core	e - Layer 6		N	A		5/4/2024	NA	NA	NA
8536	Rolled on roof core	e - Layer 7		N	A		5/4/2024	NA	NA	NA
Relinquished By:	17			Received	ву:	1200				
Printed Name	Eric Flen .			Printed Na	ame Ja	ckie ta	199			
Date/Time:	5-5-24 129			Date/Time	: L	4124	0500			
Relinguished By:	_	-		Received	By:					
Printed Name				Printed Na	ame					
Date/Time:				Date/Time):				Lab For	ms

Ver. 2016-06-27

CHAIN OF CUSTODY

Γ

٦



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

٦

Company: Alta Environmental/NV5			(Lab) Order No. つルにんはつて					
Project Number:	RSCC-24-12223			699091	7			
Project Name:								
SAMPLE ID	SAMPLE TYPE	LOCATION	Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)		
8537	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA		
8538	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA		
8539	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA		
8540	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA		
8541	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA		
8542	Rolled on roof core - Layer 6	NA	5/4/2024	NA	NA	NA		
8543	Rolled on roof core - Layer 7	NA	5/4/2024	NA	NA	NA		
8544	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA		
8545	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA		
8546	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA		
8547	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA		
8548	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA		
8549	Rolled on roof core - Layer 6	NA	5/4/2024	NA	NA	NA		
Relinquished By:	47	Received By:	AN	1	L			
Printed Name	Fre flor	Printed Name	activ Pay 19					
Date/Time:	5-5-14 12	Date/Time: 5/	14/24 0800					
Relinguished Bv:		Received By:						
Printed Name	17	Printed Name		M	Lab For	ns 27		
Date/Time:		Pabete/Tinoaf:						



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building C
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458442	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test I	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458442-001						
8055	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Cellulose Fiber Bituminous Matrix Metallic Paint Binder/Filler	<1% 5% 55% 10% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% 7	Fotal %Asbestos:	No Asbestos Detected
2458442-002						
8056	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Bituminous Matrix Metallic Paint Binder/Filler	35% 10% 53%	Chrysotile	2%
	Asbestos Present: Yes	Tot	al % Non-Asbestos:	98.0%	Fotal %Asbestos:	2.0%
2458442-003 8057	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Metallic Paint Bindor/Fillor	2% 40% 15% 40%	Chrysotile	3%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	97.0% T	Fotal %Asbestos:	3.0%
2458442-004						
8058	Rolled on roof core - Layer 1, White/ Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Bituminous Matrix Binder/Filler	30% 40% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	ן 100.0%	Fotal %Asbestos:	No Asbestos Detected
2458442-005 8059	Rolled on roof core - Layer 2, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix/Filler	20% 5% 73%	Chrysotile	2%
	Asbestos Present: Yes	Tot	al % Non-Asbestos:	98.0%	Fotal %Asbestos:	2.0%
2458442-006 8060	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 78%	Chrysotile	2%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	98.0% ך	Fotal %Asbestos:	2.0%



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building C
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458442	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report						
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
2458442 007						
8061	Rolled on roof core - Layer 4, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Cellulose Fiber Bituminous Matrix	5% 10% 85%	None Detected	
	Asbestos Present: No	Total % Non-Asbestos:		100.0% Total %Asbestos:		No Asbestos Detected
2458442-008						
8062	Rolled on roof core - Layer 5, Beige, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 35% 50%	None Detected	
	Asbestos Present: No	Total % Non-Asbestos:		100.0% T	Fotal %Asbestos:	No Asbestos Detected
2458442-009						
8063	Rolled on roof core - Layer 6, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	<1% 50%	Chrysotile	50%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	50.0% T	Total %Asbestos:	50.0%
2458442-010						
8064	Rolled on roof core - Layer 7, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	<1% 50%	Chrysotile	50%
	Asbestos Present: Yes	Total % Non-Asbestos:		50.0% T	Total %Asbestos:	50.0%
2458442-011						
8065	Rolled on roof core - Layer 1, White/ Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Metallic Paint Bituminous Matrix Binder/Filler	20% <1% 5% 55% 20%	None Detected	
	Asbestos Present: No	Total % Non-Asbestos:		100.0%]	Fotal %Asbestos:	No Asbestos Detected
2458442-012						
8066	Rolled on roof core - Layer 2, Silver/ Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix	15% 5% 80%	Chrysotile	<1%
	Asbestos Present: Yes	Total % Non-Asbestos:		100.0% T	Fotal %Asbestos:	<1%



Alta Environme	ntal	Project Number	RSCC-24-12223		
3777 Long Beach Blvd.		Project Name	Building C		
Long Beach, C	A 90807	Location	Santa Ana, CA		
Attn.: Eric Fleming		PO Number			
Report Number	2458442	WO Number			
Date Received	05/06/2024	Date Sampled	05/04/2024		
Date Analyzed	05/07/2024	Sampled By			
Date Reported	05/07/2024	Total Samples	20		

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report							
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)	
2458442-013 8067	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Bituminous Matrix	15% 5% 80%	None Detected		
	Asbestos Present: No	Total % Non-Asbestos:		100.0% Total %Asbestos:		No Asbestos Detected	
2458442-014 8068	Rolled on roof core - Layer 4, Beige, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 35% 50%	None Detected		
	Asbestos Present: No	Total % N		100.0% Total %Asbestos:		No Asbestos Detected	
2458442-015							
8069	Rolled on roof core - Layer 5, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	<1% 50%	Chrysotile	50%	
	Asbestos Present: Yes	Total % Non-Asbestos:		50.0% Total %Asbestos:		50.0%	
2458442-016 8070	Rolled on roof core - Layer 1, White/ Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Cellulose Fiber Metallic Paint Bituminous Matrix Quartz/Gravel Binder/Filler	20% 5% <1% 5% 40% 10% 20%	None Detected		
	Asbestos Present: No	Total % Non-Asbestos:		100.0% Total %Asbestos:		No Asbestos Detected	
2458442-017 8071	Rolled on roof core - Layer 2, Silver/Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Metallic paint Bituminous Matrix	40% 5% 55%	None Detected		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected	



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Beach Blvd.		Project Name	Building C
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Fleming		PO Number	
Report Number	2458442	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

SIS 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report						
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458442-018						
8072	Rolled on roof core - Layer 3, Silver/ Black, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Synthetic Fiber Metallic Paint Bituminous Matrix	5% 10% 5% 5% 75%	None Detected	
	Asbestos Present: No	Total % Non-Asbestos:		100.0% Total %Asbestos:		No Asbestos Detected
2458442-019						
8073	Rolled on roof core - Layer 4, Beige, Non-homogeneous	LAYER 1	Fibrous Glass	15%	None Detected	
		100%	Quartz/Gravel Bituminous Matrix/Filler	35% 50%		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected
2458442-020						
8074	Rolled on roof core - Layer 5, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	70.0% T	otal %Asbestos:	30.0%

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

notma 2Tabatt

R TESTING NVLAP Lab Code 500044-0

Analyst - Cristina Tabatt

Approved Signatory Cristina E. Tabatt


Relinquished By:

Relinquished By:

Printed Name

Date/Time:

Printed Name

Date/Time:

Eric Flow

5-5-24 120

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax

		// 251						services@A0	200-2773 P	m
		(Lab) Or	der No.	2458	5442					
	CUSTOMER INFO	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ann	ex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming	Fleming				Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5.	com								
			PROJECT	INFORMA	TION					
Project Name:	Building C			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PL	M	P	CM	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	-82-020	NIOSH 74	00A 🗆	s s	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	00B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		B	ulk Sample		Wipe			
SAMPLE ID	SAMPLE TY	PE		LOCAT	TON		Date	Start Time	Ava	Volume
OANI LE ID	Orivir EE 11			LOOM			Sampled	Stop Time	Flow Rate	(L)
8055	White and black roo	of mastic		N	Ą		5/4/2024	NA	NA	NA
8056	White and black roo	of mastic		N	4		5/4/2024	NA	NA	NA
8057	White and black ro	of mastic		N	Ą		5/4/2024	NA	NA	NA
8058	Rolled on roof core	- Layer 1		N	Ą		5/4/2024	NA	NA	NA
8059	Rolled on roof core	- Layer 2		N	Ą		5/4/2024	NA	NA	NA
8060	Rolled on roof core	- Layer 3		N	Ą		5/4/2024	NA	NA	NA
8061	Rolled on roof core	- Layer 4		N	4		5/4/2024	NA	NA	NA
8062	Rolled on roof core	- Layer 5	8	N	4		5/4/2024	NA	NA	NA
8063	Rolled on roof core	- Layer 6		N	4		5/4/2024	NA	NA	NA
8064	Rolled on roof core	- Layer 7		N	4		5/4/2024	NA	NA	NA

Date/Time:

Received By:

Printed Name

Date/Time:

Received By:

Printed Name

ackie TRY 17

0800

5/6/24

٢



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

1

Company: Alta Environmental/NV5			(Lab) Order No	71150	1111-2	
Project Number:	RSCC-24-12223			2932	44C	
Project Name:						
SAMPLE ID	SAMPLE TYPE	LOCATION	Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
8065	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA
8066	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA
8067	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA
8068	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA
8069	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA
8070	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA
8071	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA
8072	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA
8073	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA
8074	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA
Relinquished By:	61	Received By:	aran			
Printed Name	En-Flow	Printed Name	Jackie Tayng			
Date/Time:	5-5-24 120	Date/Time:	5/6/24 080	0		
Relinquished By:		Received By:				
Printed Name		Printed Name		Vi	Lab For	ns 27
Date/Time:		PaDete/Tinmf:		Ve		



Alta Environme	ntal	Project Number	RSCC-24-12223	
3777 Long Beach Blvd.		Project Name Building		
Long Beach, CA 90807		Location	Santa Ana, CA	
Attn.: Eric Flemi	ng	PO Number		
Report Number	2458484	WO Number		
Date Received	05/06/2024	Date Sampled	05/04/2024	
Date Analyzed	05/07/2024	Sampled By		
Date Reported	05/07/2024	Total Samples	6	

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test F	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458484-001						
8619	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 35% 55%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% To	otal %Asbestos:	No Asbestos Detected
2458484-002						
8620	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 35% 55%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% To	otal %Asbestos:	No Asbestos Detected
2458484-003						
8621	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% To	otal %Asbestos:	No Asbestos Detected
2458484-004						
8622	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	5% 25% 70%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% To	otal %Asbestos:	No Asbestos Detected
2458484-005						
8623	Mastic, White/Black, Non-	LAYER 1	Fibrous Glass	25%	None Detected	
	nomogeneous	100%	Other Non-Fibrous Material	25% 50%		
Asbestos Present: No T		Tota	Total % Non-Asbestos:		otal %Asbestos:	No Asbestos Detected
2458484-006						
8624	Mastic, White/Black/Grey, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	<1% 20% 80%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% To	otal %Asbestos:	No Asbestos Detected



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming

Report Number 2458484

 Date Received
 05/06/2024

 Date Analyzed
 05/07/2024

 Date Reported
 05/07/2024

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building C110

Santa Ana, CA

05/04/2024

6

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report								
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	S		
Sample No.	Description	Layer %	Components	(%)	Туре	(%)		

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Custma 2Tabatt

NVLAP Lab Code 500044-0

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) C	order No. 24	158484						
	CUSTOMER INF	ORMATIC	DN N	Turnaround	Time	Shipp	ed By	Repo	ort Send Via	a:
Company	NV5			Same Day		FedEx		Web		1.02
Address	3777 Long Beach	Blvd., An	nex Bldg.	1 Day		UPS		Emai		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verba		
Office Phone	562-495-5777			5 Day		Drop Boy		Mai		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special Ins	structions:		-	1 1011 01		
Email	eric.fleming@nv5	.com]						
			PROJECT	INFORMAT	ΓΙΟΝ					
Project Name:	Building C110			PO Number	r:					
Project Number:	RSCC-24-12223			Work Order	No.:	18 18				
Location:	Santa Ana, CA			Sampled By	Y:	19				
PL	M	ТР	CM	T	MOLD			LEAD	(DL)	
PLM EPA 600/M4-82-020 NIOSH 7400A		Sr	ore Trap		Air					
PLM 400 Pt. Cour	PLM 400 Pt. Count (<0.25%) NIOSH 7400B		400B 🗆	Та	ipe Lift		Paint		TILO	
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		Bu	ulk Sample		Wipe			
				S	wab		Soil			
SAMPLE ID	SAMPLE TY	PE		LOCATI	ON		Date	Start Time	Avg	Volume
	+						Sampled	Stop Time	Flow Rate	(L)
8619	Roof core	0.	NA			5/4/2024	NA	NA	NA	
8620	Roof core			NA			5/4/2024	NA	NA	NA
8621	Roof core			NA			5/4/2024	NA	NA	NA
8622	Black and white	mastic		NA	(5/4/2024	NA	NA	NA
8623	Black and white	mastic		NA			5/4/2024	NA	NA	NA
8624	Black and white	mastic		NA			5/4/2024	NA	NA	NA
							1			
Relinquished By:	Ge -			Received By	r: C.Y	m				
Printed Name F	Fre Flon			Printed Nam	e de	ackie TA	100			
Date/Time: 5	- 5-24 121	2		Date/Time:	5	16/24	0800)		
Relinquished By:				Received By	<i>r</i> :					
Printed Name				Printed Nam	<u>م</u>					
Date/Time:				Date/Time:	0				Lab Farm	
Parol Hillo.				Date/Time.					Lab Form	IS



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Beach Blvd.		Project Name	Building C111
Long Beach, CA 90807		Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458482	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/08/2024	Sampled By	
Date Reported	05/08/2024	Total Samples	12

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report										
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)				
2458482-001										
8601	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	<1% 75% 25%	None Detected					
	Asbestos Present: No		al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected				
2458482-002										
8602	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Bituminous Matrix Binder/Filler	20% 80%	None Detected					
	Asbestos Present: No		al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected				
2458482-003										
8603	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	5% 65% 30%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected				
2458482-004										
8604	Rolled on roof core - Layer 1, White/ Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Bituminous Matrix Binder/Filler	30% 40% 30%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected				
2458482-005										
8605	Rolled on roof core - Layer 2, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	15% 85%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected				
2458482-006										
8606	Rolled on roof core - Layer 3, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 80%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected				



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Beach Blvd.		Project Name	Building C111
Long Beach, CA 90807		Location	Santa Ana, CA
Attn.: Eric Fleming		PO Number	
Report Number	2458482	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/08/2024	Sampled By	
Date Reported	05/08/2024	Total Samples	12

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test I	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458482-007 8607	Rolled on roof core - Layer 1, White/ Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Synthetic Fiber Bituminous Matrix Binder/Filler	5% 30% 50% 15%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458482-008						
8608	Rolled on roof core - Layer 2, Gray, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 40% 45%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458482-009						
8609	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	30% 70%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458482-010						
8610	Rolled on roof core - Layer 1, White/	LAYER 1	Synthetic Fiber Fibrous Glass	30% <1%	None Detected	
	black, Nor-Homogeneous	100 %	Bituminous Matrix Binder/Filler	40% 30%		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458482-011						
8611	Rolled on roof core - Layer 2, Beige, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 20% 65%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458482-012						
8612	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	20% 80%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming

Report Number 2458482

 Date Received
 05/06/2024

 Date Analyzed
 05/08/2024

 Date Reported
 05/08/2024

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building C111

Santa Ana, CA

05/04/2024

12

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report									
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos				
Sample No.	Description	Layer %	Components	(%)	Туре	(%)			

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

marTabatt CustmarTabatt

Approved Signatory Cristina E. Tabatt

TESTING NVLAP Lab Code 500044-0



Γ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

٦

		(Lab) O	rder No. 2	458482	2					
	CUSTOMER INFO	ORMATIO	N	Turnaround	d Time	Shippe	d By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:	1.0000		1		
Email	eric.fleming@nv5.	ming@nv5.com								
		_	PROJECT	INFORMA	TION		_			
Project Name:	Building C111	_		_PO Numbe	er:					_
Project Number:	RSCC-24-12223	-		_Work Orde	er No.:	2				
Location:	Santa Ana, CA			_Sampled B	iy:		_			_
PLI	M	P	СМ	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4-82-020 ✓ NIOSH 7400A □ PLM 400 Pt. Count (<0.25%)		S	pore Trap		Air		TTLC			
		Т	ape Lift		Paint					
PLM 1000 Pt. Count (<0.1%)		B	ulk Sample		Wipe					
CAMPLE ID	CAMPLE TY	DE			Swab		Soil		1	
SAWFLE ID SAWFLE ITTE		LUCAT	ION		Date	Start Time	Avg	Volume		
							Sampled	NA	riow Rate	(L)
8601	Black and white	mastic	NA			5/4/2024		NA	NA	
8602	Black and white	mastic		NA	4		5/4/2024	NA	NA	NA
8603	Black and white	mastic		NA	Ą		5/4/2024	NA	NA	NA
8604	Rolled on roof core	- Layer 1		NA			5/4/2024	NA	NA	NA
8605	Rolled on roof core	- Layer 2	4	NA	NA		5/4/2024	NA	NA	NA
8606	Rolled on roof core	- Layer 3		NA	NA		5/4/2024	NA	NA	NA
8607	Rolled on roof core	- Layer 1		NA	Ą		5/4/2024	NA	NA	NA
8608	Rolled on roof core	Lavor 2		NI	A		E/4/2024	NA	NA	NIA
0000				197	`		5/4/2024	NA		NA
8609	Rolled on roof core	- Layer 3		N/	4		5/4/2024		NA	NA
8610	Rolled on roof core	- Layer 1		NA	A .		5/4/2024		NA	NA
Relinquished By:	60			Received E	By: C	NOV	ð			
Printed Name	Eric Flom	-		Printed Na	me 🤳	ackie T	5419			
Date/Time:	5-5-24 12	G		Date/Time:		5/6/24	087	0		
Relinquished By:				Received E	By:					
Printed Name				Printed Na	me					
Date/Time:				Date/Time:				ns		

Ver. 2016-06-27



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

Company:	Alta Environmental/NV5			(Lab)	Order No	01158118	27	
Project Number:	RSCC-24-12223			(200)	ordor rto.	299090	12	
Project Name:								
SAMPLE ID	SAMPLE TYPE		LOCATION		Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
8611	Rolled on roof core - Layer 2		NA		5/4/2024	NA	NA	NA
8612	Rolled on roof core - Layer 3		NA		5/4/2024	NA	NA	NA
Relinquished By:	62		Received By:	MAN	Ø			
Printed Name	Eric Flor		Printed Name	Jackieta	Lyng			
Date/Time:	5-5-24 120		Date/Time:	576/24	0800			
Relinquished By:			Received By:					
Printed Name			Printed Name			Ve	Lab Forr	ns 27
Date/Time:		Р	a Dete/Tinos:					



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building D
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458444	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

19518 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)			
2458444-001 8075	Roof mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Bituminous Matrix Binder/Filler	85% 15%	None Detected				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected			
2458444-002 8076	Roof mastic, White/Silver/ Black, Non- homogeneous	LAYER 1 100%	Cellulose Fiber Metallic Paint Bituminous Matrix Binder/Filler	<1% 10% 50% 37%	Chrysotile	3%			
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	97.0% To	otal %Asbestos:	3.0%			
2458444-003 8077	Roof mastic, White/Silver/ Black, Non- homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Bituminous Matrix Binder/Filler	20% 5% 60% 15%	None Detected				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected			
2458444-004 8078	Rolled on roof core - Layer 1, White/Silver/Black, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Synthetic Fiber Metallic Paint Bituminous Matrix Binder/Filler	5% 10% 10% 5% 40% 30%	Chrysotile	<1%			
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	100.0% To	otal %Asbestos:	<1%			
2458444-005 8079	Rolled on roof core - Layer 2, White/Silver/Black, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Metallic Paint Bituminous Matrix/Filler	15% 10% 5% 70%	Chrysotile	<1%			
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	<1%			



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building D
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458444	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

Sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458444-006 8080	Rolled on roof core - Layer 3, Beige, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Quartz/Gravel Bituminous Matrix	30% 30% 40%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-007 8081	Rolled on roof core - Layer 4, Black, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Bituminous Matrix/Filler	5% 10% 85%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-008 8082	Rolled on roof core - Layer 5, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	5% 95%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-009 8083	Rolled on roof core - Layer 1, White/ Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Metallic Paint Bituminous Matrix Binder/Filler	30% 5% 5% 45% 15%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-010 8084	Rolled on roof core - Layer 2, Silver/ Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Metallic Paint Bituminous Matrix	40% 10% 50%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-011 8085	Rolled on roof core - Layer 3, Silver/ Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix	30% 5% 65%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building D
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458444	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458444-012								
8086	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 80%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-013								
8087	Rolled on roof core - Layer 5, Beige, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 35% 50%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-014								
8088	Rolled on roof core - Layer 6, Black	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	40% 60%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-015								
8089	Rolled on roof core - Layer 7, Black/ Brown, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%		
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	70.0%	Total %Asbestos:	30.0%		
2458444-016								
8090	Rolled on roof core - Layer 1,	LAYER 1	Synthetic Fiber	25% 10%	None Detected			
	White/Black/Silver, Non-homogeneous	100%	Metallic Paint	10%				
			Bituminous Matrix Binder/Filler	40% 15%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458444-017								
8091	Rolled on roof core - Layer 2, Silver/ Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix	35% 15% 50%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building D
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458444	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	20

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Method of Analysis Determination of Asbestos in Bulk Building Materials.

Test Report									
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)			
	·		•	()	,	()			
2458444-018				000/					
8092	Rolled on roof core - Layer 3, Black,	LAYER 1	Fibrous Glass	20%	None Detected				
	Homogeneous	100%	Bituminous Matrix	80%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected			
2458444-019									
8093	Rolled on roof core - Layer 4, Gray,	LAYER 1	Fibrous Glass	15%	None Detected				
	Non-homogeneous	100%	Quartz/Gravel	40%					
			Bituminous Matrix/Filler	45%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected			
2458444-020									
8094	Rolled on roof core - Layer 5,	LAYER 1	Cellulose Fiber	20%	Chrysotile	30%			
	Brown/Black, Homogeneous	100%	Bituminous Matrix	50%					
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	70.0% T e	otal %Asbestos:	30.0%			

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

ma stabatt Custma stabatt

Approved Signatory Cristina E. Tabatt

CA-ELAP #2823

TESTING NVLAP Lab Code 500044-0



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No.	2458444
-----------------	---------

			1	1		1		
	CUSTOMER INFORMATIO	N	Turnaround Time	Shippe	ed By	Repo	rt Send Via	:
Company	NV5		Same Day	FedEx		Web		
Address	3777 Long Beach Blvd., Ar	inex Bldg.	1 Day 🗖	UPS		Email		
City/State/Zip	Long Beach, Ca 90807		2 Day 🗆	USPS		Fax		
Contact	Eric J. Fleming		3 Day 🗆	Drop Off		Verbal		
Office Phone	562-495-5777		5 Day 🗆	Drop Box		Mail		
Cell			Weekend 🗆	Other		Pick up		
Fax	562-495-5877		Special Instruction	ns:				
Email	eric.fleming@nv5.com							
			-					
		PROJECT	INFORMATION					
Project Name:	Building D		PO Number:					
Project Number:	RSCC-24-12223		Work Order No .:					
Location:	Santa Ana, CA		Sampled By:					
BI	M	CM	MOLD			LEAD	(Db)	
	-82-020 MIOSH		Spore Trai		Air			
PLM 400 Pt. Cour	nt (<0.25%) □ NIOSH	400B	Tape Lift		Paint		TILO	_
PLM 1000 Pt. Co.	unt (<0.1%)		Bulk Same		Wipe			1.1
	, ,		Swab		Soil			
SAMPLE ID	SAMPLE TYPE	1	LOCATION		Date	Start Time	Avg	Volume
					Sampled	Stop Time	Flow Rate	(L)
8075	White/black roof mastic		NA	0	5/4/2024	NA	NA	NA
8076	White/black roof mastic		NA		5/4/2024	NA	NA	NA
8077	White/black roof mastic		NA		5/4/2024	NA	NA	NA
8078	Rolled on roof core - Layer 1		NA		5/4/2024	NA	NA	NA
8079	Rolled on roof core - Layer 2		NA		5/4/2024	NA	NA	NA
8080	Rolled on roof core - Layer 3		NA		5/4/2024	NA	NA	NA
8081	Rolled on roof core - Layer 4		NA	-	5/4/2024	NA	NA	NA
8082	Rolled on roof core - Layer 5		NA		5/4/2024	NA	NA	NA
8083	Rolled on roof core - Layer 1		NA		5/4/2024	NA	NA	NA
8084	Rolled on roof core - Layer 2		NA		5/4/2024	NA	NA	NA
Relinquished By:	62		Received By:	nom	/			
Printed Name	Et a Flomin		Printed Name	Jackarta	5411			
Date/Time: 5	-5-24 12 "		Date/Time:	5/6/24	0800	7		
Relinquished By:			Received By:					
Printed Name			Printed Name					
Date/Time:			Date/Time:	<i>R</i>			Lab Form	ns



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

Company:	Alta Environmental/NV5	1.1		(1 ab) (Order No	OUT	QUILI	
Project Number	: RSCC-24-12223			(Lab)	order No.	245	8994	
Project Name:]					
SAMPLE ID	SAMPLE TYPE		LOCATION		Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
8085	Rolled on roof core - Layer 3		NA		5/4/2024	NA	NA	NA
8086	Rolled on roof core - Layer 4		NA		5/4/2024	NA	NA	NA
8087	Rolled on roof core - Layer 5		NA		5/4/2024	NA	NA	NA
8088	Rolled on roof core - Layer 6		NA		5/4/2024	NA	NA	NA
8089	Rolled on roof core - Layer 7		NA		5/4/2024	NA	NA	NA
8090	Rolled on roof core - Layer 1		NA		5/4/2024	NA	NA	NA
8091	Rolled on roof core - Layer 2		NA		5/4/2024	NA	NA	NA
8092	Rolled on roof core - Layer 3		NA		5/4/2024	NA	NA	NA
8093	Rolled on roof core - Layer 4		NA		5/4/2024	NA	NA	NA
8094	Rolled on roof core - Layer 5		NA		5/4/2024	NA	NA	NA
		1.0						
Relinquished By:	61		Received By:	AN				
Printed Name	Eric Flow's		Printed Name Joc	kie TA.	1-17			
Date/Time:	5 5 24 1200		Date/Time:	124	0800			
Relinquished By:			Received By:				2	
Printed Name			Printed Name			Ve	Lab Form	ns 27
Date/Time:		Pa	Bjete/Tinno≸:					-1



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building D 106 & 107
Long Beach, CA 90807		Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458477	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	6

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test I	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
2458477-001						
8571	Roof core, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	<1% 80% 20%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458477-002						
8572	Roof core, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	30% 40% 30%	None Detected	
	Asbestos Present: No	Total % Non-Asbestos:		100.0% Total %Asbestos:		No Asbestos Detected
2458477-003						
8573	Roof core, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	20% 20% 60%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458477-004						
8574	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	10% 50% 40%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458477-005						
8575	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	5% 50% 45%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458477-006						
8576	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	15% 45% 40%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report										
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	i				
Sample No.	Description	Layer %	Components	(%)	Туре	(%)				

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

marTabatt CustmarTabatt

TESTING NVLAP Lab Code 500044-0

Analyst - Cristina Tabatt

Approved Signatory Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

٦

		(Lab) O	rder No. 🖓	158477						
	CUSTOMER INF	ORMATIC)N	Turnaround	Time	Shippe	ed By	Repo	rt Send Via	a:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., An	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	.com		-						
			PROJECT	INFORMA	TION					
Project Name:	Building D106&107			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Order	r No.:	× .				
Location:	Santa Ana, CA			_Sampled B	y:					
PI	LM	P	CM	Т	MOLD			LEAD	(Pb)	
PLM EPA 600/M	4-82-020	NIOSH 7	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	Int (<0.25%)	NIOSH 7	400B	Ta	ape Lift		Paint			
PLM 1000 Pt. Count (<0.1%)			Bi	ulk Sample		Wipe				
SAMPLE ID	SAMPLET	/DE	T	10004	Wab		Soli		T Aug	Litelumo
SAMPLE ID	SAWFLE ID SAWFLE ITFE		LUGAN	ION		Sampled	Stan Time	Avg	Volume	
							Sampled	NA	Flow Mate	(L)
8571	Roof core	1		NA	•		5/4/2024		NA	NA
8572	Roof core	1		NA	4		5/4/2024	NA	NA	NA
8573	Roof core	l.		NA			5/4/2024	NA	NA	NA
8574	White and black	mastic		NA	NA		5/4/2024	NA	NA	NA
8575	White and black	mastic		NA	NA			NA	NA	NA
8576	White and black	mastic		NA	4		5/4/2024	NA	NA	NA
Relinquished By:	60			Received B	y: C.	Man	Y			
Printed Name	Eril Flomi			Printed Nar	ne Ja	TUKIE TZ	1411	_		
Date/Time:	6-5-24 1	20		Date/Time:		576/24	080	0		
Relinguished By:				Received B	v:					
Printed Name				Printed Nar	<u>,</u>					
Date/Time:				Date/Time:	10				Lob Forr	
Date/ mile.				Date/Time.					Lab Form	15



Alta Environme	ntal	Project Number	RSCC-24-12223	
3777 Long Beach Blvd.		Project Name		
Long Beach, C	A 90807	Location	Santa Ana, CA	
Attn.: Eric Flemi	ng	PO Number		
Report Number	2458478	WO Number		
Date Received	05/06/2024	Date Sampled	05/04/2024	
Date Analyzed	05/07/2024	Sampled By		
Date Reported	05/07/2024	Total Samples	6	

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test F	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458478-001						
8577	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458478-002						
8578	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458478-003						
8579	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458478-004						
8580	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix OtHer Non-Fibrous Materia	15% 35% I 50%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458478-005						
8581	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix OtHher Non-Fibrous Materi	5% 65% al 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Total %Asbestos:		No Asbestos Detected
2458478-006						
8582	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix OtHher Non-Fibrous Materi	15% 35% al 50%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming

Report Number 2458478

 Date Received
 05/06/2024

 Date Analyzed
 05/07/2024

 Date Reported
 05/07/2024

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building D108

Santa Ana, CA

05/04/2024

6

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report									
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	;			
Sample No.	Description	Layer %	Components	(%)	Туре	(%)			

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Custma 2Tabatt

NVLAP Lab Code 500044-0

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No. 24	158478						
	CUSTOMER INF	ORMATIO	N	Turnaround	d Time	Shippe	ed By	Repo	rt Send Via	:
Company	NV5			Same Dav		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Dav		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Dav		USPS		Fax	5	
Contact	Eric J. Fleming			3 Dav		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:			Tion up		
Email	eric.fleming@nv5	.com								
			PROJECT	INFORMA	TION					
Project Name:	Building D108			PO Numbe	er:					
Project Number: RSCC-24-12223			Work Orde	r No.:						
Location:	Santa Ana, CA			Sampled B	y:					
			CM		HOLD					
					MOLD	_	Air		(Pb)	
PLM 400 Pt. Count (<0.25%)		400B 🗆	Т	ape Lift		Paint		TILO		
			В	ulk Sample		Wipe				
		5	Swab		Soil					
SAMPLE ID SAMPLE TYP		'PE		LOCAT	ION		Date	Start Time	Avg	Volume
						×	Sampled	Stop Time	Flow Rate	(L)
8577	Roof core	te -		N	Ą		5/4/2024	NA	NA	NA
8578	Roof core			NA			5/4/2024	NA	NA	NA
8579	Roof core	E)		NA			5/4/2024	NA	NA	NA
8580	White and black	mastic		NA			5/4/2024	NA	NA	NA
8581	White and black	mastic		NA	Ą		5/4/2024	NA	NA	NA
8582	White and black	mastic		NA	4		5/4/2024	NA	NA	NA
	1									
Relinquished By:	41			Received E	sy: M	And				
Printed Name	Eric Flom!			Printed Na	me Ű	actie To	5479			
Date/Time: 5	5-5-24 12	4		Date/Time:	5	6/24	0801	2		
Relinquished By:				Received By:						
Printed Name				Printed Na	me					
Date/Time:				Date/Time:					Lab Forn	ns

Ver. 2016-06-27



Alta Environme	ntal	Project Number	RSCC-24-12223		
3777 Long Bea	ch Blvd.	Project Name	Building D109		
Long Beach, C	A 90807	Location	Santa Ana, CA		
Attn.: Eric Flemi	ng	PO Number			
Report Number	2458479	WO Number			
Date Received	05/06/2024	Date Sampled	05/04/2024		
Date Analyzed	05/08/2024	Sampled By			
Date Reported	05/08/2024	Total Samples	6		

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test F	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458479-001						
8583	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 65% 25%	None Detected	
	Asbestos Present: No	Tota	I % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected
2458479-002						
8584	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Bituminous Matrix Other Non-Fibrous Material	65% 25%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected
2458479-003						
8585	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 70% 10%	None Detected	
	Asbestos Present: No	Tota	I % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected
2458479-004						
8586	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	15% 25% 60%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected
2458479-005						
8587	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	5% 20% 75%	None Detected	
	Asbestos Present: No		al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected
2458479-006						
8588	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	15% 25% 60%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Tc	otal %Asbestos:	No Asbestos Detected



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming **Report Number** 2458479

 Date Received
 05/06/2024

 Date Analyzed
 05/08/2024

 Date Reported
 05/08/2024

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building D109

Santa Ana, CA

05/04/2024

6

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report									
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	5			
Sample No.	Description	Layer %	Components	(%)	Туре	(%)			

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Custma 2Tabatt

TESTING NVLAP Lab Code 500044-0

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt



Γ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No.2L	158479						
	CUSTOMER INF	ORMATIC	N	Turnaround	Time	Shippe	ed By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., An	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special Instructions:						
Email	eric.fleming@nv5	.com		_						
			PROJECT	INFORMA	TION					
Project Name:	Building D109			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PL	M	Р	CM	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4-82-020 Image: Construction of the second seco		S	pore Trap		Air		TTLC			
		NIOSH 7	400B 🗆	Ta	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		B	ulk Sample		Wipe			
SAMPLEID	SAMPLE T	/DE			wab		Soil			
SAWFLEID	SAWFLE IT	FE		LUCAT	ION		Date	Start Time	Avg	Volume
0502	Destau			b.	0		Campied	NA	1 IOW IVALE	(=)
0000	Roor core			INA	`		5/4/2024		NA	NA
8584	Roof core			NA			5/4/2024	NA	NA	NA
8585	Roof core			NA		5/4/2024	NA	NA	NA	
8586	White and black	mastic		NA			5/4/2024	NA	NA	NA
8587	White and black	mastic		NA	NA			NA	NA	NA
8588	White and black	mastic		NA			5/4/2024	NA	NA	NA
Relinquished By:	En la			Received B	y:	Ano	Y			
Printed Name	Eri- Flon	11-		Printed Nan	ne Ja	chie Ta	yny			
Date/Time:	5-5-24 120			Date/Time:	C	76/24	0800	7		
Relinquished By:				Received By:						
Printed Name				Printed Nan	ne		14			
Date/Time:				Date/Time: Lab Forms						

.

Ver. 2016-06-27



Alta Environme	ntal	Project Number	RSCC-24-12223			
3777 Long Beach Blvd.		Project Name				
Long Beach, C	A 90807	Location Santa Ana,				
Attn.: Eric Flemi	ng	PO Number				
Report Number	2458445	WO Number				
Date Received	05/06/2024	Date Sampled	05/04/2024			
Date Analyzed	05/07/2024	Sampled By				
Date Reported	05/07/2024	Total Samples	6			

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report										
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)				
2458445-001										
8095	Roof core, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	<1% 70% 30%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% Total %Asbestos		No Asbestos Detected				
2458445-002										
8096	Roof core, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	5% 70% 25%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected				
2458445-003										
8097	Roof core, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	5% 65% 30%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected				
2458445-004										
8098	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	10% 50% 40%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected				
2458445-005										
8099	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	20% 60% 20%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected				
2458445-006										
8100	Mastic, White/ Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Binder/Filler	40% 40% 20%	None Detected					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T e	otal %Asbestos:	No Asbestos Detected				



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming

Report Number 2458445

 Date Received
 05/06/2024

 Date Analyzed
 05/07/2024

 Date Reported
 05/07/2024

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building D110

Santa Ana, CA

05/04/2024

6

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report									
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos				
Sample No.	Description	Layer %	Components	(%)	Туре	(%)			

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

magTabatt CustmagTabatt

Approved Signatory Cristina E. Tabatt

TESTING NVLAP Lab Code 500044-0



Γ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) Order No. 2458445								
	CUSTOMER INFO	RMATIO	N	Turnaround	Time	Shippe	d By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5.	com		-						
	1		PROJECT	INFORMA	TION					
Project Name:	Building D110			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PL	M	P	СМ	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4-82-020		400A 🗆	S	pore Trap		Air		TTLC		
		NIOSH 74	400B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Cou	unt (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
SAMPLEID					Swab		Soll	Ctert Time	A	Maluma
			LUCAT			Sampled	Ston Time	Flow Rate	volume	
8095	Roof core			NA		5/4/2024	NA	NA	NA	
8096	Roof core			NA	NA		5/4/2024	NA	NA	NA
8097	Roof core			NA			5/4/2024	NA	NA	NA
8098	White and black r	nastic		NA			5/4/2024	NA	NA	NA
8099	White and black r	nastic		NA	4		5/4/2024	NA	NA	NA
8100	White and black r	nastic		NA	A		5/4/2024	NA	NA	NA
<										
									-	
							~			
Relinquished By:	4			Received B	y: (Mon	0			
Printed Name	Fire Plem.			Printed Nar	ne Jac	ckie Th	417			
Date/Time:	5-5-24 1	20		Date/Time:	5	14/24	0800			
Relinquished By:				Received B	y:					
Printed Name				Printed Nar	ne		1			
Date/Time:				Date/Time:					Lab Form	ns



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building D111
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458481	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	6

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test F	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458481-001 8595	Roof core, White/Black, Homogeneous	; LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458481-002 8596	Roof core, White/Black, Homogeneous	; LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458481-003 8597	Roof core, White/Black, Homogeneous	; LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458481-004 8598	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass BiTnder/Filler OtHher Non-Fibrous Materi	30% 30% al 40%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458481-005 8599	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass BiTnder/Filler OtHher Non-Fibrous Materi	30% 30% al 40%	None Detected	
	Asbestos Present: No	Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
2458481-006 8600	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass BiTnder/Filler OtHher Non-Fibrous Materi	30% 30% al 40%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Alta Environmental 3777 Long Beach Blvd. Long Beach, CA 90807 Attn.: Eric Fleming

Report Number 2458481

 Date Received
 05/06/2024

 Date Analyzed
 05/07/2024

 Date Reported
 05/07/2024

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Project Number RSCC-24-12223

Building D111

Santa Ana, CA

05/04/2024

6

Project Name

Location

PO Number WO Number

Date Sampled

Total Samples

Sampled By

Test Report										
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	S				
Sample No.	Description	Layer %	Components	(%)	Туре	(%)				

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Custma 2Tabatt

NVLAP Lab Code 500044-0

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No. 24	458481						
	CUSTOMER INFO	RMATIO	N	Turnaround	Time	Shippe	d By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email	A	
Citv/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell		_		Weekend		Other		Pick up		
Fax	562-495-5877			Special In:	structions:			1		
Email	eric.fleming@nv5.	com		1						
			PROJECT	INFORMA	TION					
Project Name:	Building D111			PO Numbe	r:				and a state of a provident	
Project Number:	Project Number: RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana. CA			- Sampled B	v:					
					·					
PL	_M	P	CM		MOLD	_	Ale	LEAD	(Pb)	
PLM EPA 600/M4	PLM EPA 600/M4-82-020		5	pore Trap		Air		TILC		
PLM 1000 Pt. Count (<0.1%) W/TWA		В	ulk Sample		Wipe					
			S	Swab		Soil				
SAMPLE ID SAMPLE T		PE		LOCAT	ION		Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
8595	Roof core			NA	Ą		5/4/2024	NA	NA	NA
8596	Roof core	111		NA	Ą		5/4/2024	NA	NA	NA
8597	Roof core	1.1		NA		5/4/2024	NA	NA	NA	
8598	White and black	mastic		NA			5/4/2024	NA	NA	NA
8599	White and black	mastic		NA	NA			NA	NA	NA
8600	White and black	mastic		NA	4		5/4/2024	NA	NA	NA
Relinquished By:	m			Received E	зу: С	Man	Y			due or the second
Printed Name	Eric Flomis			Printed Na	me	Jackie.	Tay11			
Date/Time:	5-5-24 124			Date/Time:		5/6/24	080	D		
Relinquished By:				Received E	By:					
Printed Name				Printed Na	me					
Date/Time:				Date/Time: Lab Forms						

Ver. 2016-06-27



Alta Environme	ntal	Project Number	RSCC-24-12223			
3777 Long Beach Blvd.		Project Name	Building D112			
Long Beach, C	A 90807	Location Santa Ana				
Attn.: Eric Flemi	ng	PO Number				
Report Number	2458480	WO Number				
Date Received	05/06/2024	Date Sampled	05/04/2024			
Date Analyzed	05/07/2024	Sampled By				
Date Reported	05/07/2024	Total Samples	6			

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report										
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)					
2458480-001											
8589	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected						
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected					
2458480-002											
8590	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	10% 60% 30%	None Detected						
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected					
2458480-003											
8591	Roof core, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	15% 55% 30%	None Detected						
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected					
2458480-004											
8592	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	35% 35% 30%	None Detected						
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected					
2458480-005											
8593	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	40% 35% 25%	None Detected						
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected					
2458480-006											
8594	Mastic, White/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	40% 35% 25%	None Detected						
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected					



05/07/2024

Alta EnvironmentalPro3777 Long Beach Blvd.ProLong Beach, CA 90807LooAttn.: Eric FlemingPOReport Number 2458480WODate Received 05/06/2024DateDate Analyzed 05/07/2024Sam

Project NumberRSCC-24-12223Project NameBuilding D112LocationSanta Ana, CAPO NumberVO NumberDate Sampled05/04/2024Sampled By6

Method of Analysis

Date Reported

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report										
Laboratory ID	Sample Location	Layer No.	. Non-Asbestos Asbestos			;				
Sample No.	Description	Layer %	Components	(%)	Туре	(%)				

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Custma 2Tabatt

NVLAP Lab Code 500044-0

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No. 2	158480						
	CUSTOMER INFO	RMATIO	N	Turnaround	Time	Shippe	d By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email	P	
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special Ins	structions:					
Email	eric.fleming@nv5.	com		1						
			PROJECT	INFORMA	TION					
Project Name:	Building D112			PO Numbe	r:					
Project Number:	Project Number: RSCC-24-12223			Work Orde	No.:					
Location:	Santa Ana, CA			Sampled B	y:					
			014		MOLD		_	1540	(DL)	
			5	MOLD		Air		(PD)		
PLM 400 Pt. Cou	PLM 400 Pt. Count (<0.25%)		400B	Ta	ape Lift		Paint		TIEO	_
PLM 1000 Pt. Count (<0.1%) w/ TWA			В	ulk Sample		Wipe				
			S	wab		Soil				
SAMPLE ID SAMPLE TYPE			LOCAT	ION		Date	Start Time	Avg	Volume	
							Sampled	Stop Time	Flow Rate	(L)
8589	Roof core			NA			5/4/2024	NA	NA	NA
8590	Roof core			NA	NA		5/4/2024	NA	NA	NA
8591	Roof core			NA			5/4/2024	NA	NA	NA
8592	White and black	mastic		NA	NA			NA	NA	NA
8593	White and black	mastic		NA	\		5/4/2024	NA	NA	NA
8594	White and black	mastic		NA	4		5/4/2024	NA	NA	NA
							11			
							2			4
									-	
Relinquished By:	40			Received E	y: A	An	-			
Printed Name Eric Flom			Printed Na	me J1	CKIE TA.	159				
Date/Time:	5-5-24 17	- 0,		Date/Time:		576/24	0800	>		
Relinquished By:				Received E	sy:					
Printed Name				Printed Na	me					
Date/Time:				Date/Time: Lab Forms						

Ver. 2016-06-27



Alta Environmental		Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building E
Long Beach, CA 90807		Location	Santa Ana, CA
Attn.: Eric Fleming		PO Number	
Report Number	2458469	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report						
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458469-001						
8101	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	5% 80% 15%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-002						
8102	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	5% 80% 15%	None Detected	
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-003						
8103	Roof mastic, White/Silver/Black, Non- homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	5% 82% 10%	Chrysotile	3%
	Asbestos Present: Yes	Tot	al % Non-Asbestos:	97.0%	Total %Asbestos:	3.0%
2458469-004						
8104	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-005						
8105	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-006						
8106	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Alta Environmental		Project Number	RSCC-24-12223
3777 Long Beach Blvd.		Project Name	Building E
Long Beach, CA 90807		Location	Santa Ana, CA
Attn.: Eric Fleming		PO Number	
Report Number	2458469	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

is 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report						
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458469-007 8107	Rolled on roof core - Layer 1, White/Silver/Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	25% 10% 40% 25%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-008 8108	Rolled on roof core - Layer 2, Silver/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	15% 80% 5%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-009 8109	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-010						
8110	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-011						
8111	Rolled on roof core - Layer 5, White/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	15% 65% 20%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458469-012						
8112	Rolled on roof core - Layer 6, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected


Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building E
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458469	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458469-013								
8113	Rolled on roof core - Layer 6, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-014 8114	Rolled on roof core - Layer 1, White/Silver/Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Materia	25% 10% 45% I 20%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-015								
8115	Rolled on roof core - Layer 2, Silver/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Materia	15% 70% I 15%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-016								
8116	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-017								
8117	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	10% 90%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-018								
8118	Rolled on roof core - Layer 5, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass	40% <1%	None Detected			
			Bituminous Matrix	60%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building E
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458469	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	 Non-Asbestos Components 	(%)	Asbestos Type	(%)		
2458469-019								
8119	Rolled on roof core - Layer 6, White/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	5% 70% 25%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-020								
8120	Rolled on roof core - Layer 1, White/Black/Silver, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Bituminous Matrix Other Non-Fibrous Material	25% 10% 45% 20%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-021								
8121	Rolled on roof core - Layer 2, Black/Silver, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	10% 85% 5%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-022								
8122	Rolled on roof core - Layer 3, Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	15% 85%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458469-023								
8123	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	50% 25%	Chrysotile	25%		
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	75.0%	Total %Asbestos:	25.0%		
2458469-024 8124	Rolled on roof core - Layer 5, White/Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler Other Non-Fibrous Material	15% 60% 25%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building E
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458469	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report							
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)	
2458469-025 8125	Rolled on roof core - Layer 6, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	50% 25%	Chrysotile	25%	
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	75.0% To	tal %Asbestos:	25.0%	

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

CA-ELAP #2823

allaba

TESTING

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt

NVLAP Lab Code 500044-0



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

٦

		(Lab) O	rder No. 2	458469						
	CUSTOMER INF	ORMATIC	N	Turnaround	Time	Shippe	ad By	Repo	ort Send Via	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., An	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell			1.1	Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	.com]						
			PROJECT	INFORMA	TION					
Project Name:	Building E			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			_Sampled B	y:					
PL	M	Р	CM	T	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	1-82-020	NIOSH 7	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	400B 🗆	Ta	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		B	ulk Sample		Wipe			
			1	S	wab		Soil		1	
SAMPLE ID	SAMPLE IT	PE		LOCATION		Date	Start Time	Avg	Volume	
					_		Sampleo	Stop Time	Flow Rate	(L)
8101	White and black roo	of mastic		NA			5/4/2024		NA	NA
8102	White and black ro	of mastic		NA	•	11	5/4/2024	NA	NA	NA
8103	White and black ro	of mastic		NA	N N		5/4/2024	NA	NA	NA
8104	Black roof ma	stic		NA	1		5/4/2024	NA	NA	NA
8105	Black roof ma	stic		NA			5/4/2024	NA	NA	NA
8106	Black roof ma	stic		NA			5/4/2024	NA	NA	NA
8107	Rolled on roof core	- Layer 1		NA			5/4/2024	NA	NA	NA
8108	Rolled on roof core	- Layer 2		NA			5/4/2024	NA	NA	NA
8109	Rolled on roof core	- Layer 3		NA	L.		5/4/2024	NA	NA	NA
8110	Rolled on roof core	- Layer 4		NA			5/4/2024	NA	NA	NA
Relinquished By:	40			Received B	y: 🤇	nan				
Printed Name	Eric Flomis			Printed Nan	ne Jai	195 TEN	11			
Date/Time:	5-5-24 17	4		Date/Time:	51	6/24	0800			
Relinguished By:				Received B	v:					
Printed Name				Printed Nan	ne			-		
Date/Time:				Date/Time:						
Date/Time.				Date/Time.					Lab Form	15



Company:	Alta Environmental/NV5		(Lab) Order No (ILEQUIL9		
Project Number:	RSCC-24-12223			955761		
Project Name:						
SAMPLE ID	SAMPLE TYPE	LOCATION	Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
8111	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA
8112	Rolled on roof core - Layer 6	NA	5/4/2024	NA	NA	NA
8113	Rolled on roof core - Layer 7	NA	5/4/2024	NA	NA	NA
8114	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA
8115	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA
8116	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA
8117	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA
8118	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA
8119	Rolled on roof core - Layer 6	NA	5/4/2024	NA	NA	NA
8120	Rolled on roof core - Layer 1	NA	5/4/2024	NA	NA	NA
8121	Rolled on roof core - Layer 2	NA	5/4/2024	NA	NA	NA
8122	Rolled on roof core - Layer 3	NA	5/4/2024	NA	NA	NA
8123	Rolled on roof core - Layer 4	NA	5/4/2024	NA	NA	NA
8124	Rolled on roof core - Layer 5	NA	5/4/2024	NA	NA	NA
8125	Rolled on roof core - Layer 6	NA	5/4/2024	NA	NA	NA
		A				
Relinquished By:	le	Received By:	NAND			
Printed Name	Firk Flemin	Printed Name	ackie Tayng			
Date/Time: 5	-5-24 175	Date/Time:	5/4/24 080	10		
Relinquished By:		Received By:				
Printed Name		Printed Name		Ve	Lab Forn	1S 27
Date/Time:		Pagete/Timef:				ada



Alta Environme	ntal	Proj	ject Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Proj	ject Name	Building F
Long Beach, C	A 90807	Loc	ation	Santa Ana, CA
Attn.: Eric Flemi	ing	PO	Number	
Report Number	2458473	WO	Number	
Date Received	05/06/2024	Date	e Sampled	05/04/2024
Date Analyzed	05/07/2024	San	npled By	
Date Reported	05/07/2024	Tota	al Samples	25

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)			
2458473-001 8129	Roof mastic, White/Silver/Black, Non-	LAYER 1	Fibrous Glass	<1%	Chrysotile	4%			
	homogeneous	100%	Bituminous Matrix Metallic Paint Binder/Filler	50% 10% 36%	·				
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	96.0% T o	otal %Asbestos:	4.0%			
2458473-002									
8130	Roof mastic, White/Silver/Black, Non-	LAYER 1	Fibrous Glass	5%	Chrysotile	3%			
	homogeneous	100%	Bituminous Matrix	60%					
			Metallic Paint Binder/Filler	5% 27%					
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	97.0% T o	otal %Asbestos:	3.0%			
2458473-003									
8131	Roof mastic, White/Silver/Black, Non-	LAYER 1	Cellulose Fiber	15%	None Detected				
	homogeneous	100%	Metallic Paint	10%					
			Bituminous Matrix Binder/Filler	45% 30%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected			
2458473-004									
8132	Roof mastic, Black, Homogeneous	LAYER 1	Cellulose Fiber	15%	None Detected				
		100%	Bituminous Matrix/Filler	85%					
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected			
2458473-005									
8133	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix/Filler	15% 85%	None Detected				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected			
2458473-006									
8134	Roof mastic, Black, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix/Filler	15% 85%	None Detected				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected			



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building F
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ing	PO Number	
Report Number	2458473	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)			
2458473-007 8135	Rolled on roof core - Layer 1, White/Black/Silver, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Metallic Paint Bituminous Matrix Binder/Filler	30% 10% 10% 40% 10%	None Detected				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected			
2458473-008 8136	Rolled on roof core - Layer 2, Black, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 80%	None Detected				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected			
2458473-009 8137	Rolled on roof core - Layer 3, Beige, Non-homogeneous	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	15% 35% 50%	None Detected				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected			
2458473-010 8138	Rolled on roof core - Layer 4, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%			
	Asbestos Present: Yes	Tot	al % Non-Asbestos:	70.0% T	otal %Asbestos:	30.0%			
2458473-011 8139	Rolled on roof core - Layer 5, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%			
	Asbestos Present: Yes	Tot	al % Non-Asbestos:	70.0% T	otal %Asbestos:	30.0%			
2458473-012 8140	Rolled on roof core - Layer 1, White/Black/Silver, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Fibrous Glass Bituminous Matrix Metallic Paint Binder/Filler	30% 5% 40% 5% 20%	None Detected				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected			



Alta Environme	ntal	Project Nun	nber RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Nan	1e Building F
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	,
Report Number	2458473	WO Numbe	r
Date Received	05/06/2024	Date Sampl	ed 05/04/2024
Date Analyzed	05/07/2024	Sampled By	/
Date Reported	05/07/2024	Total Samp	les 25

sis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458473-013 8141	Rolled on roof core - Layer 2, Silver/ Black, Non-homogeneous	LAYER 1 100%	Fibrous Glass Metallic Paint Bituminous Matrix	20% 5% 75%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458473-014								
8142	Rolled on roof core - Layer 3, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 80%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458473-015								
8143	Rolled on roof core - Layer 4, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix	20% 80%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458473-016								
8144	Rolled on roof core - Layer 5, Gray	LAYER 1 100%	Fibrous Glass Quartz/Gravel Bituminous Matrix/Filler	20% 35% 45%	None Detected			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T	otal %Asbestos:	No Asbestos Detected		
2458473-017								
8145	Rolled on roof core - Layer 6, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%		
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	70.0% T	otal %Asbestos:	30.0%		
2458473-018								
8146	Rolled on roof core - Layer 7, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%		
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	70.0% T	otal %Asbestos:	30.0%		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building F
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458473	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25

is 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

Test Report								
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458473-019								
8147	Rolled on roof core - Layer 1,	LAYER 1	Synthetic Fiber	40%	None Detected			
	White/Silver/Black, Non-homogeneous	100%	Metallic Paint	5%				
			Bituminous Matrix Binder/Filler	35% 20%				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458473-020								
8148	Rolled on roof core - Layer 2, Silver/	LAYER 1	Fibrous Glass	15%	None Detected			
	Black, Non-homogeneous	100%	Metallic Paint Bituminous Matrix	5% 80%				
				0070				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458473-021								
8149	Rolled on roof core - Layer 3, Black,	LAYER 1	Fibrous Glass	20%	None Detected			
	Non-nomogeneous	100%	Bituminous Matrix	80%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458473-022								
8150	Rolled on roof core - Layer 4, Black,	LAYER 1	Cellulose Fiber	40%	None Detected			
	Non-homogeneous	100%	Bituminous Matrix	60%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458473-023								
8151	Rolled on roof core - Layer 5, Gray,	LAYER 1	Fibrous Glass	20%	None Detected			
	Non-homogeneous	100%	Quartz/Gravel Bituminous Matrix/Filler	40% 40%				
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		
2458473-024								
8152	Rolled on roof core - Layer 6, Gray,	LAYER 1	Fibrous Glass	15%	None Detected			
	Non-homogeneous	100%	Quartz/Gravel Bituminous Matrix/Filler	40% 45%				
	Asbestos Present: No	Tot	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected		



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building F
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458473	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	25
Method of Analy	sis 40 CFR Part 763 Appendix E to Subpart E, EPA Metho	d 600/M4-82-020; u	pdated method 600

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report							
Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)		
2458473-025 8153	Rolled on roof core - Layer 7, Black/ Brown, Homogeneous	LAYER 1 100%	Cellulose Fiber Bituminous Matrix	20% 50%	Chrysotile	30%		
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	70.0% To	tal %Asbestos:	30.0%		

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

allabat

CA-ELAP #2823

12Tabatt Cur

Analyst - Cristina Tabatt

Approved Signatory Cristina E. Tabatt

TESTING NVLAP Lab Code 500044-0



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No. 21	158473						
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By Report Send Via:		:	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:	1		1		
Email	eric.fleming@nv5	.com								
			PROJECT	INFORMA	TION					
Project Name:	Building F			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
	M	D	CM	T	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 74	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 7	400B 🗆	Ta	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
				S	wab		Soil			
SAMPLE ID	SAMPLE T	YPE		LOCAT	ION		Date	Start Time	Avg	Volume
		_					Sampled	Stop Time	Flow Rate	(L)
8129	White and black re	oof mastic		NA		5/4/2024		NA	NA	
8130	White and black re	oof mastic		NA			5/4/2024	NA	NA	NA
8131	White and black ro	oof mastic		NA	4		5/4/2024	NA	NA	NA
8132	Black roof m	astic		NA	4		5/4/2024	NA	NA	NA
8133	Black roof m	astic		NA	A		5/4/2024	NA	NA	NA
8134	Black roof m	astic		NA	4		5/4/2024	NA	NA	NA
8135	Rolled on roof core	e - Layer 1		NA	4		5/4/2024	NA	NA	NA
8136	Rolled on roof core	e - Layer 2		NA	A		5/4/2024	NA	NA	NA
8137	Rolled on roof core	e - Layer 3		NA	4		5/4/2024	NA	NA	NA
8138	Rolled on roof core	e - Layer 4		NA	4		5/4/2024	NA	NA	NA
Relinquished By:	10			Received B	iy: ()	m	/			
Printed Name	Eric Fin	1 5		Printed Nar	ne Jad	tie Tay.	79			
Date/Time:	5-5-26 1	20		Date/Time:	5161	24 0	500			
Relinquished Bur				Received P	W.				e:	
Drinted Marrie				Drinted Mar					x	
Printed Name				Printed Name						
Date/Time:				Date/Time:				Ve	Lab Forr er. 2016-06-	ns 27

Page ____ of ____



Company:	Alta Environmental/NV5			(Lab) (rder No	211-0117	2	
Project Number:	RSCC-24-12223			(Luo) C		245891	3	
Project Name:								
SAMPLE ID	SAMPLE TYPE	LOC	ATION		Date Sampled	Start Time Stop Time	Avg Flow Rate	Volum (L)
8139	Rolled on roof core - Layer 5		NA		5/4/2024	NA	NA	NA
8140	Rolled on roof core - Layer 1		NA		5/4/2024	NA	NA	NA
8141	Rolled on roof core - Layer 2		NA		5/4/2024	NA	NA	NA
8142	Rolled on roof core - Layer 3		NA		5/4/2024	NA	NA	NA
8143	Rolled on roof core - Layer 4		NA		5/4/2024	NA	NA	NA
8144	Rolled on roof core - Layer 5		NA		5/4/2024	NA	NA	NA
8145	Rolled on roof core - Layer 6		NA		5/4/2024	NA	NA	NA
8146	Rolled on roof core - Layer 7		NA		5/4/2024	NA	NA	NA
8147	Rolled on roof core - Layer 1		NA		5/4/2024	NA	NA	NA
8148	Rolled on roof core - Layer 2		NA		5/4/2024	NA	NA	NA
8149	Rolled on roof core - Layer 3		NA		5/4/2024	NA	NA	NA
8150	Rolled on roof core - Layer 4		NA		5/4/2024	NA	NA	NA
8151	Rolled on roof core - Layer 5		NA		5/4/2024	NA	NA	NA
8152	Rolled on roof core - Layer 6		NA		5/4/2024	NA	NA	NA
8153	Rolled on roof core - Layer 7		NA		5/4/2024	NA	NA	NA
Relinquished By:	61	Received	d By:	Em		_		
Printed Name	FIL Flenin	Printed N	Name Jac	okie Tan	199			
Date/Time:	5-5-24 120	Date/Tim	1e: 57	6/24	0800			
Relinquished By:		Received	d By:					
Printed Name		Printed N	Name			M	Lab Form	ns 27
Date/Time:		Pagete/Tim	of:					



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Building G
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458471	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/07/2024	Sampled By	
Date Reported	05/07/2024	Total Samples	3

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

	Test Report						
Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	. Non-Asbestos Components	(%)	Asbestos Type	(%)	
2458471-001							
8126	Roof core, White/ Black, Non-	LAYER 1	Fibrous Glass	15%	None Detected		
	homogeneous	100%	Bituminous Matrix	55%			
			Binder/Filler	30%			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T (otal %Asbestos:	No Asbestos Detected	
2458471-002							
8127	Roof core, White/ Black, Non-	LAYER 1	Fibrous Glass	15%	None Detected		
	homogeneous	100%	Bituminous Matrix	60%			
			Binder/Filler	25%			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected	
2458471-003							
8128	Roof core, White/ Black, Non-	LAYER 1	Fibrous Glass	20%	None Detected		
	homogeneous	100%	Bituminous Matrix Binder/Filler	60% 20%			
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0% T o	otal %Asbestos:	No Asbestos Detected	

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

CA-ELAP #2823

Tabatt

(R) TESTING NVLAP Lab Code 500044-0

Analyst - Cristina Tabatt

Approved Signatory Cristina E. Tabatt



		(Lab) O	rder No. 24	158471						
	CUSTOMER INFO	RMATIO	N	Turnaround	Time	Shippe	ed By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Dav		Drop Off		Verbal		
Office Phone	562-495-5777			5 Dav		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:	Touror		1 rion up		
Email	eric.fleming@nv5.	com								
				1						
			PROJECT	INFORMA	TION					
Project Name:	Building G			PO Numbe	r:					
Project Number:	r: RSCC-24-12223		_Work Orde	r No.:						
Location:	Santa Ana, CA			_Sampled B	y:					
PI	LM	P	CM	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M	4-82-020	NIOSH 74	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	int (<0.25%)	NIOSH 74	400B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Co	ount (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
	CAMPLE TY				wab		Soli			Maluma
SAMPLE ID	SAMPLE IY	PE		LUCAT	ION		Date	Start Time	Avg	volume
							Sampled	NA	Flow Rate	(L)
8126	Roof core		NA		5/4/2024		NA	NA		
8127	Roof core			NA		5/4/2024	NA	NA	NA	
8128	Roof core			NA	Ą		5/4/2024	NA	NA	NA
Relinguished By:	10			Received F	iv: C	non	6	1		
Printed Name	E. Flow's			Printed Na	me la	ACCE TO	5411			
Date/Time:	5-5-24 120			Date/Time:	5	16/24	0800			
Relinguished By:				Received F	By:	et l				
Printed Name				Printed Na	me					
Date/Time:				Date/Time:					Lab Form	ms



Alta Environme	ntal	Project Number	RSCC-24-12223
3777 Long Bea	ch Blvd.	Project Name	Sheds
Long Beach, C	A 90807	Location	Santa Ana, CA
Attn.: Eric Flemi	ng	PO Number	
Report Number	2458483	WO Number	
Date Received	05/06/2024	Date Sampled	05/04/2024
Date Analyzed	05/08/2024	Sampled By	
Date Reported	05/08/2024	Total Samples	6

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test I	Report			
Laboratory ID Sample No.	Sample Location Description	Layer No Layer %	o. Non-Asbestos Components	(%)	Asbestos Type	(%)
2458483-001						
8613	Rolled on roof core - Layer 1, Grey/Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Bituminous Matrix Other Non-Fibrous Materia	30% 50% al 20%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458483-002						
8614	Rolled on roof core - Layer 2, Black, Non-homogeneous	LAYER 1 100%	Bituminous Matrix/Filler	95%	Chrysotile	5%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	95.0%	Total %Asbestos:	5.0%
2458483-003						
8615	Rolled on roof core - Layer 1, Grey/Black, Non-homogeneous	LAYER 1 100%	Synthetic Fiber Bituminous Matrix Other Non-Fibrous Materia	30% 50% al 20%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458483-004						
8616	Rolled on roof core - Layer 2, Black, Non-homogeneous	LAYER 1 100%	Bituminous Matrix/Filler Other Non-Fibrous Materia	72% al 25%	Chrysotile	3%
	Asbestos Present: Yes	Tota	al % Non-Asbestos:	97.0%	Total %Asbestos:	3.0%
2458483-005						
8617	Rolled on roof core - Layer 1,	LAYER 1	Synthetic Fiber	30%	None Detected	
	Grey/Black, Non-homogeneous	100%	Bituminous Matrix Other Non-Fibrous Materia	50% al 20%		
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected
2458483-006						
8618	Rolled on roof core - Layer 2, Black, Homogeneous	LAYER 1 100%	Fibrous Glass Bituminous Matrix/Filler	15% 85%	None Detected	
	Asbestos Present: No	Tota	al % Non-Asbestos:	100.0%	Total %Asbestos:	No Asbestos Detected



Project Number RSCC-24-12223 Alta Environmental **Project Name** Sheds 3777 Long Beach Blvd. Long Beach, CA 90807 Location Santa Ana, CA Attn.: Eric Fleming **PO Number WO Number** Report Number 2458483 05/06/2024 05/04/2024 Date Received **Date Sampled** 05/08/2024 Date Analyzed Sampled By **Date Reported** 05/08/2024 **Total Samples** 6

Method of Analysis

40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116 Determination of Asbestos in Bulk Building Materials.

		Test Re	port			
Laboratory ID	Sample Location	Layer No.	Non-Asbestos		Asbestos	5
Sample No.	Description	Layer %	Components	(%)	Туре	(%)

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed. CA-ELAP #2823

Custma 2Tabatt

TESTING NVLAP Lab Code 500044-0

Analyst - Fred Chappelear

Approved Signatory Cristina E. Tabatt



Γ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No. 24	158483						
	CUSTOMER INFO	ORMATIO	N	Turnaround	Time	Shippe	ed By	Repo	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	.com		-						
			PROJECT	INFORMA	TION					
Project Name:	Sheds			PO Numbe	er:					
Project Number:	RSCC-24-12223			Work Orde	er No.:					
Location:	Santa Ana, CA			Sampled E	By:					
DI	M		CM		MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 7	400A 🗆	s	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 7	400B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		E	ulk Sample		Wipe			
					Swab		Soil			
SAMPLE ID	SAMPLE TY	PE		LOCAT	TION		Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
8613	Rolled on roof core	- Layer 1		N	٩		5/4/2024		NA	NA
8614	Rolled on roof core	- Layer 2		N	Ą		5/4/2024	NA	NA	NA
8615	Rolled on roof core	- Layer 1		N	4		5/4/2024	NA	NA	NA
8616	Rolled on roof core	- Layer 2		N	٩		5/4/2024	NA	NA	NA
8617	Rolled on roof core	- Layer 1		N	4		5/4/2024	NA	NA	NA
8618	Rolled on roof core	- Layer 2		N	Ą		5/4/2024	NA	NA	NA
					2					
Relinquished By:	20			Received E	By:	m	-			
Printed Name	Fii- Flomit			Printed Na	me Jack	ie tay.	11			
Date/Time:	5-5-24 12			Date/Time:	5/0	124	0800			
Relinquished By:				Received E	By:					
Printed Name				Printed Na	me			1		
Date/Time:				Date/Time:		1			Lab Form	ns

Ver. 2016-06-27

NV5

Lead



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building A Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	3

Analytical Method: EPA 7420/3050

2458454

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

	Lead (Pb) in	Paint by Flame AAS	
Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)
2458454-001 5169	Paint Chip	0.1018	< 49
2458454-002 5170	Paint Chip	0.1025	< 49
2458454-003 5171	Paint Chip	0.1061	< 47

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



Г

CHAIN OF CUSTODY

		(Lab) O	rder No.	24581	454		-			
	CUSTOMER INFO	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day	A	UPS		Email	P	
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5.	com		1						
				1						
			PROJECT	INFORMA	TION					
Project Name:	Building A			PO Numbe	er:					
Project Number:	RSCC-24-12223			- VVORK Orde	er No.:					
Lab) Order No. 24'SE 4'S'4 CUSTOMER INFORMATION Turnaround Time Shipped By Report Send Via: Address 3777 Long Beach, Ca 90807 2 Day UPS Email										
PL	M	P	СМ		MOLD			LEAD	(Pb)	
PLM EPA 600/M4	-82-020	NIOSH 74	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cour	nt (<0.25%)	NIOSH 74	400B	00B		Paint				
PLM 1000 Pt. Co	unt (<0.1%)	W/ IWA				Wipe				
SAMPLEID		PE		LOCAT			Date	Start Time	Ava	Volume
SAMPLE ID	SAMPLE II			LOOKI			Sampled	Stop Time	Flow Rate	
					oumpieu	NA	1 IOW FRATE	(=)		
5169	Paint Chip			N	Ą		5/4/2024		NA	NA
5170	Paint Chip			N	A		5/4/2024	NA	NA	NA
5171	Paint Chip			N	A		5/4/2024	NA	NA	NA
		_								Via: Via: Volume (L) NA NA NA NA NA NA NA
Relinquished By:	les			Received I	By: C	nav	T			
Printed Name	Eric Flomin	5		Printed Na	me 🔇	Ackie To	TY19			
Date/Time: 4	-5-24 120	2		Date/Time	:	5/6/24	Ost	00		
Relinquished By:				Received I	By:	-				
Printed Name			per les	Printed Na	me					
Date/Time:				Date/Time	:				Lab Forr	ms



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building B Location: Santa Ana, CA

Date Sampled: 5/	4/2024
Sampled By:	
Total Samples: 3	

Analytical Method: EPA 7420/3050

2458453

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

	Lead (Pb) in	Paint by Flame AAS	
Lab ID	Location/Description	Sample Weight	Lead Concentration
Client ID	Location/Description	(g)	ppm (mg/kg)
2458453-001		0.4004	450
5166	Paint Chip	0.1031	150
2458453-002	Deint Ohin	0.4020	- 40
5167	Paint Chip	0.1038	< 48
2458453-003		0.4005	. 50
5168	Paint Chip	0.1005	< 50

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



		(Lab) Oi	rder No.	24584	53					
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ann	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	.com]						
	1		PROJECT	INFORMA	TION					
Project Name:	Building B			PO Numbe	ir:					
Project Number:	RSCC-24-12223	25		Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PI	M	P	СМ	T	MOLD	1		LEAD	(Pb)	
PLM EPA 600/M4	4-82-020 🗆	NIOSH 74	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	400B 🗆	т	ape Lift		Paint			
Image: Customer No. Customer No. Customer No. Customer No. Turnaround Time Shipped By Report Send Vit Address 3777 Long Beach Bivd., Annex Bidg. 1 Day UPS Email Fac. Web Fac. Fac.										
	1			1004	Swab		Soil		A	N/stars
SAMPLE ID	SAMPLE TY	PE		LOCA	ION		Date	Start Time	Avg	Volume
							Sampleo	NA	FIOW Rate	(L)
5166	Paint Chi	0		N	4		5/4/2024		NA	NA
5167	Paint Chip	0		N	4		5/4/2024	NA	NA	NA
5168	Paint Chi	0		N	4		5/4/2024	NA	NA	NA
Address 3777 Long Beach Bilvd., Annex Bidg. 1 Day I DPS Email Email Email City/State/Zip Long Beach, Ca 90807 2 Day UPS Fax T City/State/Zip Long Beach, Ca 90807 3 Day Drop Off Verbal Mail Contact Eric J. Fleming 3 Day Drop Off Verbal Mail Cell S62:495-5877 Special Instructions: Pick up Mail Fax S62:495-5877 Special Instructions: Pick up Pick up Project Number: RSC-24-12223 Work Order No: Coation: Santa Ana, CA Sampled By: PLM EPA 600/M4-82-020 NIOSH 7400A Spore Trap Air TTLC Paint Z PLM 100 PL Count (<0.1%)										
Relinquished By:	93			Received I	By: Ch	And				
Printed Name	Eric Flon	i'a		Printed Na	me	ACKIE TO	5479			
Date/Time:	5-5-20 12	4		Date/Time	: .	16/24	0800)		
Relinguished By				Received I	By:					
Printed Name				Printed Na	me					
Date/Time				Date/Time					Lab For	ms
Salor Inno.										



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Project Number: RSCC-24-12223 Project Name: Building C Location: Santa Ana, CA

Date Sampled: 5/4/2024

Date Received:	5/6/2024	Date Sampled: 5/4
Date Analyzed:	5/7/2024	Sampled By:
Date Reported:	5/7/2024	Total Samples: 4

Analytical Method: EPA 7420/3050

2458446

Reporting Limit: 5.0 µg Pb

	Lead (Pb) in	Paint by Flame AAS		
Lab ID	Location/Description	Sample Weight	Lead Concentration	
Client ID	Location/Description	(g)	ppm (mg/kg)	
2458446-001	Deint Chin	0.1000	- 10	
4680	Paint Chip	0.1020	< 49	
2458446-002	Deint Chin	0.0000	4.50	
4681	Paint Chip	0.0890	< 30	
2458446-003	Deint Chin	0.1000	- 40	
4682	Paint Chip	0.1026	< 49	
2458446-004	Deint Chin	0.1000	- 40	
4683	Paint Chip	0.1090	< 46	

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



		_
21158446		

		(Lab) O	rder No.	2458	146		-			
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca S	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		1.1
Fax	562-495-5877			Special In	structions:			1		
Email	eric.fleming@nv5	.com		1						
				1			_			
			PROJECT	INFORMA	TION					
Project Name:	Building C		_	PO Numbe	r:					
Project Number:	RSCC-24-12223		_	Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PL	_M	P	СМ		MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 74	100A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	100B	T	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	W/ TWA		В	ulk Sample		Wipe			
SAMPLEID	SAMPLETY	DE		LOCAT			Data	Start Time	Ava	Volumo
SAWFLEID	SAMPLE			LUCAI			Sampled	Ston Time	Flow Rate	(L)
Los protections in the							oumpiou	NA	1 Iow Hate	(=)
4680	Paint Chi)		NA	4		5/4/2024		NA	NA
4681	Paint Chi)		NA		5/4/2024	NA	NA	NA	
4682	Paint Chip)		NA		5/4/2024	NA	NA	NA	
4683	Paint Chip)		NA	Ą		5/4/2024	NA	NA	NA
		5. K								
Relinquished By:	Gg.			Received E	by: CM	mo				
Printed Name	EricFlan	-		Printed Na	me Jac	KIC TRI	199			
Date/Time:	5-5-26 10	+ 6		Date/Time:	5	16/24	0800			
Relinquished By:				Received By:						
Printed Name				Printed Name						
Date/Time:			Date/Time: Lab Forms							



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building C110 Location: Santa Ana, CA

Date Sampled: 5/4/2024
Sampled By:
Total Samples: 2

Analytical Method: EPA 7420/3050

2458463

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS						
Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)			
2458463-001 5190	Paint Chip	0.0532	< 94			
2458463-002 5191	Paint Chip	0.0385	< 130			

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



(Lab) Order No.	245846	3
-----------------	--------	---

	CUSTOMER INFORMATION			Turnaround Time Shippe			ed By Report Send Via:			
Company	NV5 s		Same Day		FedEx		Web			
Address	3777 Long Beach	Blvd., Annex	Bldg.	1 Day		UPS		Email		12
City/State/Zip	Long Beach, Ca 9	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off	P	Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:	Tr.				
Email	eric.fleming@nv5	.com]						
	1	PF	OJECT	INFORMA	TION					
Proiect Name:	Building C110			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
DI	M	PCM		1	MOLD			LEAD	(Pb)	
	-₩ 1-82-020 □	NIOSH 7400		S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 7400	B 🗆	Т	ape Lift		Paint		TILO	
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
				S	Swab		Soil			
SAMPLE ID	SAMPLE TY	PE		LOCAT	ION		Date	Start Time	Avg	Volume
			_				Sampled	Stop Time	Flow Rate	(L)
5190	Paint Chip			NA	Ą		5/4/2024	NA	NA	NA
5191	Paint Chip	5		NA	Ą		5/4/2024	NA	NA	NA
8										
	×									
Relinquished By:	60			Received E	Ву: 🤇	harro				
Printed Name	EricFloo			Printed Na	me	ackie To	2-1-19			
Date/Time:	5-5.24 10	70		Date/Time:	:	516/24	J081	00		
Relinquished By:				Received E	Зу:					
Printed Name				Printed Na	me					
Date/Time:			Date/Time: Lab Forms							



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building C111 Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	2

2458461

5/6/2024

5/7/2024

5/7/2024

Analytical Method: EPA 7420/3050 Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS							
Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)				
2458461-001 5186	Paint Chip	0.0770	< 65				
2458461-002 5187	Paint Chip	0.0952	< 53				

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



		(Lab) O	rder No.	2458	461					
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	rt Send Via	:
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	n Blvd., Anr	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	5.com								
			PROJECT	INFORMA	TION					
Project Name:	Building C111			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PL	M	P	СМ	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 74	100A 🗆	s	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	400B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
				5	Swab		Soil			
SAMPLE ID	SAMPLE T	YPE		LOCAT	ION		Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
5186	Paint Chi	p		NA	Ą		5/4/2024	NA	NA	NA
5187	Paint Chi	p		N	4		5/4/2024	NA	NA	NA
Relinguished By:	40			Received F	By:	Am		1		I
Printed Name	Enzy Flor	al a		Printed Na	me	lachin -	BUAR			
Date/Time:	5-5.24	12-4		Date/Time:		57612	£750	800		
Relinguished By:	2			Received E	By:	101-	1			
Printed Name				Printed Na	me					
Date/Time:				Date/Time: Lab Forms						



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building D Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	3

Analytical Method: EPA 7420/3050

2458448

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS							
Lab ID	Location/Description	Sample Weight	Lead Concentration				
Client ID	Elocation/Description	(g)	ppm (mg/kg)				
2458448-001		0.4040	. 10				
4685	Paint Chip	0.1043	< 48				
2458448-002	Deint Ohin	0.1052	07				
4686	Paint Chip	0.1053	97				
2458448-003	Deint Ohin	0.1051	- 40				
4687	Paint Chip	0.1051	< 48				

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) Or	der No.	24584	48	-				
/	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via:	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:	1				
Email	eric.flemina@nv5	.com								
Lincal				1						
			PROJECT	INFORMA	TION					
Project Name:	Building D			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
PI	М	P	СМ	Т	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 74	400A 🗆	s	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	400B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
				5	Swab		Soil			
SAMPLE ID	SAMPLE T	(PE		LOCAT	ION		Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
4685	Paint Chi	þ		N	4		5/4/2024		NA	NA
4686	Paint Chi	þ		NA		5/4/2024	NA	NA	NA	
4687	Paint Chi	þ		NA			5/4/2024	NA	NA	NA
Relinguished By:	60			Received B	Ву: 🤇	non	8			
Printed Name	Eric FI	emia		Printed Na	me Jø	We Fr	111			
Date/Time:	5-5-26	120		Date/Time	5	6/24	0800			
Relinquished By				Received I	Bv:	1				
Printed Name				Printed Na	me					
Date/Time				Date/Time: Lab Forms				ms		
a second a s										

Ver. 2016-06-27



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building D106 & 107 Location: Santa Ana, CA

Date Sampled: 5/4/2024 Sampled By: Total Samples: 4

2458455

5/6/2024

5/7/2024

5/7/2024

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg Pb

	Lead (Pb) in		
Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)
2458455-001 5172	Paint Chip	0.1003	< 50
2458455-002 5173	Paint Chip	0.1026	< 49
2458455-003 5174	Paint Chip	0.0347	< 140
2458455-004 5175	Paint Chip	0.1021	< 49

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



CHAIN OF CUSTODY

		(Lab) Or	der No.	24584	55	2				
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	Shipped By		Report Send Via:	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ann	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca S	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off	\blacksquare	Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5.com			1						
			PROJECT	INFORMA	TION					
Project Name:	Building D106&107			PO Numbe	er:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	sy:					
		-						LEAD	(Db)	
PL	_M	P			MOLD		Air		TTLC	
PLM EPA 600/M4	4-82-020 □	NIOSH 7		Т	ane Lift		Paint		TILO	
PLM 400 Pt. Cou	nt(<0.25%)	W/ TWA		B	ulk Sample		Wipe			
FEW 1000 Ft. 00					Swab		Soil			
SAMPLE ID	SAMPLE T	YPE		LOCAT	TION		Date	Start Time	Avg	Volume
						Sampled	Stop Time	Flow Rate	(L)	
5172	Paint Chi	p		N	A		5/4/2024	NA	NA	NA
5173	Paint Chi	p		N	A		5/4/2024	NA	NA	NA
5174	Paint Chi	p		N	A		5/4/2024	NA	NA	NA
5175	Paint Chi	p		N	A		5/4/2024	NA	NA	NA
Relinquished By	61	,		Received	ву: Д	m				
Printed Name	Eric Flimi	~		Printed Na	ame Ja	okieta	419			
Date/Time:	5-5-24 10	F 1		Date/Time	: 51	6/24	0800			
Relinquished By	:			Received	By:					
Printed Name				Printed Na	ame					
Date/Time:				Date/Time	ə:				Lab For	ms
								V	er. 2016-06	-27



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building D108 Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	3

Analytical Method: EPA 7420/3050

2458456

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS							
Lab ID	Location/Description	Sample Weight	Lead Concentration				
Client ID	Location/Description	(g)	ppm (mg/kg)				
2458456-001		0.4040	- 10				
5176	Paint Chip	0.1018	< 49				
2458456-002	Deint Ohin	0.0000	< 220				
5177	Paint Chip	0.0230	< 220				
2458456-003	Deint Chin	0.1000	- 10				
5178	Paint Chip	0.1028	< 49				

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



		(Lab) O	rder No.	24584	54					
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Ani	nex Bldg.	1 Day		UPS		Email		
Citv/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Dav		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:			11		
Email	eric.fleming@nvt	.com		1						
			PROJECT	INFORMA	TION					
Project Name:	Building D108			PO Numbe	r:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			Sampled B	y:					
			014		MOLD			LEAD		
	_M			6	MOLD		Δir			
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 7	400B	Т	ape Lift		Paint		TILO	_
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		В	ulk Sample		Wipe			
				S	wab		Soil			
SAMPLE ID	SAMPLE T	YPE		LOCAT	ION		Date	Start Time	Avg	Volume
						-	Sampled	Stop Time	Flow Rate	(L)
5176	Paint Chi	p		NA	4		5/4/2024	NA	NA	NA
5177	Paint Chi	p		NA	4		5/4/2024	NA	NA	NA
5178	Paint Ch	p		NA	A		5/4/2024	NA	NA	NA
	1									
Relinquished By:	40			Received E	By:	AND				
Printed Name	EricFlom			Printed Na	me Ja	tokic Ta	yng			
Date/Time:	5-5-24	12		Date/Time:		5/6/24	10801	0		
Relinguished By:				Received E	By:					
Printed Name				Printed Na	me					
Date/Time:				Date/Time:					Lab For	ms



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building D109 Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	2

Analytical Method: EPA 7420/3050

2458457

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS							
Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)				
2458457-001 5179	Paint Chip	0.1020	< 49				
2458457-002 5180	Paint Chip	0.0238	< 210				

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



Γ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) Or	der No.	2458457					
	CUSTOMER INF	ORMATIO	N	Turnaround Time	Shippe	d By	Report	Send Via:	
Company	NV5			Same Day	FedEx		Web		
Address	3777 Long Beach	Blvd., Ann	ex Bldg.	1 Day	UPS		Email	A	
Citu/State/7in	Long Beach, Ca 90807			2 Day	USPS		Fax		
Contact	Eric I Eleming			3 Dav 🗆	Drop Off		Verbal		
Office Phone	562-495-5777			5 Day	Drop Box		Mail		
	002 400 0111			Weekend 🗆	Other		Pick up		
Cell	562-495-5877			Special Instructions:					
Fax	eric fleming@nv5	com							
Email	encillenning@ive			-					
			PROJECT	INFORMATION					
Project Name:	Building D109			PO Number:					
Project Number:	RSCC-24-12223			_Work Order No.:					
Location:	Santa Ana, CA			_Sampled By:					
PI	M	Р	СМ	MOLD			LEAD	(Pb)	
	4-82-020	NIOSH 7	400A 🗆	Spore Trap		Air		TTLC	
PLM 400 Pt. Cou	int (<0.25%)	NIOSH 7	400B 🗆	Tape Lift		Paint			
PLM 1000 Pt. Co	ount (<0.1%)	w/ TWA		Bulk Sample		Wipe			
				Swab		Soil			
SAMPLE ID	SAMPLE TYPE			LOCATION	Date	Start Time	Avg	Volum	
						Sampled	NA Stop Time	Flow Rate	(L)
5179	Paint Ch	p		NA		5/4/2024		NA	NA
5180	Paint Ch	p		NA	5/4/2024	NA	NA	NA	
-									
Relinquished By			1	Received By:	non	J	1		
Printed Name	Eric Flor	1 a		Printed Name	ackie Te	941			
Date/Time:	5-5-24 12	11		Date/Time:	5/6/24	0801	2		
Relinquished By	/:			Received By:					
Printed Name				Printed Name					
Date/Time:				Date/Time:				Lab Fo	rms

Ver. 2016-06-27


Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Project Number: RSCC-24-12223 Project Name: Building D110 Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	3

Date Analyzed:5/7/2024Date Reported:5/7/2024

2458449

5/6/2024

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS					
Lab ID	Location/Description	Sample Weight	Lead Concentration		
Client ID	Elocation/Description	(g)	ppm (mg/kg)		
2458449-001		0.4000	< 49		
4684	Paint Chip	0.1020			
2458449-002	Deint Ohin	0.4004			
4685	Paint Chip	0.1061	< 47		
2458449-003	Deint Ohin	0.1020	- 40		
4686	Paint Chip	0.1039	< 48		

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

	2458449
b) Order No.	4750771

		(Lab) Oi	rder No.	2458	449					
	CUSTOMER INFO	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via:	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off	P	Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	.com		1						
			PROJECT	INFORMA	TION					
Project Name:	Building D110			PO Numbe	er:					
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			- Sampled B	y:					
Loodion										
PI	_M	P	CM		MOLD	_	Air		(Pb)	- ·
PLM EPA 600/M4	4-82-020 □	NIOSH 7	400A	S T	pore i rap		Alr		TILC	
PLM 400 PL Cou	(<0.25%)	w/ TWA		В	ulk Sample		Wipe			
	unit (10.176) —			5	Swab		Soil			
SAMPLE ID	SAMPLE TY	'PE		LOCAT	ION		Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
4684	Paint Chip)		NA		5/4/2024	NA	NA	NA	
4685	Paint Chir)		NA		5/4/2024	NA	NA	NA	
4686	Paint Chip)		N	Ą		5/4/2024	NA	NA	NA
		-								
		3								
Relinquished By	60		(4)	Received I	Ву:	Agy	/			
Printed Name Etic Flomia			Printed Na	ime Ja	ackle T	2719				
Date/Time:	5-5-24	12 5		Date/Time	: 5/6	124	108	00		
Relinquished By				Received By:						
Printed Name				Printed Name						
Date/Time:			Date/Time: Lab Forms							



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building D111 Location: Santa Ana, CA

Date Sampled: 5/4/2024	
Sampled By:	
Total Samples: 2	

2458459

5/6/2024

5/7/2024

5/7/2024

Analytical Method: EPA 7420/3050 Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS					
Lab ID	Location/Description	Sample Weight	Lead Concentration		
Client ID	Locations Decemption	(g)	ppm (mg/kg)		
2458459-001	Deint Chin	0.4020	- 10		
5184	Paint Chip	0.1039	< 48		
2458459-002 5185	Paint Chip	0.1055	< 47		

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



ſ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) Or	rder No.	2458	451					
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via:	
Company Address City/State/Zip Contact Office Phone Cell Fax Email	NV5 3777 Long Beach Long Beach, Ca Eric J. Fleming 562-495-5777 562-495-5877 eric.fleming@nv8	n Blvd., Anr 90807 5.com	nex Bldg.	Same Day 1 Day 2 Day 3 Day 5 Day Weekend Special In	structions:	FedEx UPS USPS Drop Off Drop Box Other		Web Email Fax Verbal Mail Pick up		
			PPO JECT	INFORMA	TION					
Project Name: Project Number: Location:	Building D111 RSCC-24-12223 Santa Ana, CA			PO Numbe Work Orde Sampled E	er: er No.: ey:				(20)	
PLM EPA 600/M4 PLM 400 Pt. Cou PLM 1000 Pt. Co	■ 4-82-020 □ nt (<0.25%) □ unt (<0.1%) □	P NIOSH 7 NIOSH 7 w/ TWA	CM 400A 400B	S T E	MOLD pore Trap ape Lift sulk Sample Swab		Air Paint Wipe Soil		(Pb) TTLC	
SAMPLE ID	SAMPLE 1	YPE		LOCA	ΓΙΟΝ		Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
5184	Paint Ch	ip		Ν	A		5/4/2024	NA	NA	NA
5185	Paint Ch	iip		Ν	A		5/4/2024	NA	NA	NA
	5									
		3.								
-										
Relinquished By	dy			Received	By:	ans	W			
Printed Name	Eric Flemi.	1		Printed N	ame	Jacque	iny ng	Con		
Date/Time:	5-5-24 1.	ra		Date/Time	9:	5/4/24	-1	1000		
Relinquished By	1			Received	By:					
Printed Name				Printed N	ame					
Date/Time:				Date/Time	э:				Lab For	rms



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building D112 Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	3

Analytical Method: EPA 7420/3050

2458458

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS					
Lab ID	Location/Description	Sample Weight	Lead Concentration		
Client ID	Location/Description	(g)	ppm (mg/kg)		
2458458-001		0.4000	- 40		
5181	Paint Chip	0.1022	< 49		
2458458-002	Deint Ohin	0.1011	- 10		
5182	Paint Chip	0.1044	< 48		
2458458-003	Deint Ohin	0.0000	- 240		
5183	Paint Chip	0.0208	< 240		

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



٢

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) Or	rder No.	24584	428					
	CUSTOMER INF	ORMATIO	N	Turnaround	Time	Shippe	d By	Repor	t Send Via:	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:					
Email	eric.fleming@nv5	.com		1						
			PROJECT	INFORMA	TION					
Project Name:	Building D112			PO Numbe	r:	3				
Project Number:	RSCC-24-12223			Work Orde	r No.:					
Location:	Santa Ana, CA			-Sampled B	y:					
PL	_M	P	СМ		MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020	NIOSH 74	400A 🗆	S	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 74	400B	Т	ape Lift		Paint			
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		В	ulk Sample		VVipe			
	SAMPLET	VRE		LOCAT			Date	Start Time	Ανα	Volume
SAMPLE ID	SAMPLE	TPE		LOCAT			Sampled	Stop Time	Flow Rate	(L)
							Campiou	NA		(=/
5181	Paint Chi	p		N	Ą		5/4/2024		NA	NA
5182	Paint Chi	p		NA		5/4/2024	NA	NA	NA	
5183	Paint Chi	p		N	Ą		5/4/2024	NA	NA	NA
				1-		0				
Relinquished By:		/ .		Received	By: C	esta	51104			
Printed Name	Ericki	om ;		Printed Na	ime 🔾	9692-10	14 m	CON		
Date/Time:	2-5-24	125.		Date/Time	:	5/6/24	02	500		
Relinquished By				Received By:						
Printed Name				Printed Name						
Date/Time:			Date/Time: Lab Forms							

Ver. 2016-06-27



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building E Location: Santa Ana, CA

Date Sampled:	5/4/2024
Sampled By:	
Total Samples:	3

Analytical Method: EPA 7420/3050

2458450

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS					
Lab ID	Location/Description	Sample Weight	Lead Concentration		
Client ID	Location/Description	(g)	ppm (mg/kg)		
2458450-001		0.0705	100		
4686	Paint Chip	0.0765	190		
2458450-002	Deint Chin	0.1015	- 40		
4687	Paint Chip	0.1045	< 48		
2458450-003		0.4057	. 47		
4688	Paint Chip	0.1057	< 47		

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) O	rder No.	2458	\$450					
	CUSTOMER INF	ORMATIO	N	Turnaround	l Time	Shippe	d By	Repor	rt Send Via	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anr	nex Bldg.	1 Day	A	UPS		Email		3
City/State/Zip	Long Beach, Ca	90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop Off		Verbal		
Office Phone	562-495-5777			5 Day		Drop Box		Mail		
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	structions:			1		
Email	eric.fleming@nv5	.com		1						
				1						
			PROJECT	INFORMA	TION					
Project Name:	Building E			PO Numbe	ər:					
Project Number:	RSCC-24-12223	_		_Work Orde	er No.:					
Location:	Santa Ana, CA			_Sampled B	By:					
PI	M	P	CM	1	MOLD			LEAD	(Pb)	
PLM EPA 600/M4	4-82-020 🗆	NIOSH 7	400A 🗆	s	pore Trap		Air		TTLC	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 7	400B 🗆	Т	ape Lift		Paint			
PLM 1000 Pt. Co	ount (<0.1%)	w/ TWA		B	Bulk Sample		Wipe			
					Swab		Soil			1/-1
SAMPLE ID	SAMPLE T	YPE		LOCAT	TION		Date	Start Time	Avg	Volume
						Sampled	NA	Flow Rate	(L)	
4686	Paint Chi	р	NA		5/4/2024		NA	NA		
4687	Paint Chi	р		NA			5/4/2024	NA	NA	NA
4688	Paint Chi	р		N	A		5/4/2024	NA	NA	NA
		2								
Relinquished By	ho		1	Received	By:	120	/	1		
Printed Name	E. Fla	•		Printed Na	me	AL TZ	lan			
Date/Time	C-C-LI	12-12		Date/Time	5	124	19 080	0		
Polinguished Dur	2-1-04	10 41		Received	By:	1-1	000			
Drinted North	e *			Drinted Ma	by.					
Date/Times				Date/Time					Lab Eco	me
Date/Time:				Date/ I IIIe					Lab Fon	110

Ver. 2016-06-27



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building F Location: Santa Ana, CA

Date Sampled: 5/4/2024 Sampled By: Total Samples: 3

2458452

5/6/2024

5/7/2024

5/7/2024

Analytical Method: EPA 7420/3050

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS					
Lab ID	Location/Description	Sample Weight	Lead Concentration		
Client ID	Elocation/Description	(g)	ppm (mg/kg)		
2458452-001		0.4040	- 10		
4690	Paint Chip	0.1018	< 49		
2458452-002	Deint Ohin	0.1071	. 47		
4691	Paint Chip	0.1071	< 47		
2458452-003		0.1000	- 10		
4692	Paint Chip	0.1089	< 46		

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab)	Order No.	2458452
(LaD)	Order No.	2750102

	0		100						
	CUSTOMER INFORMATIO	N	Turnaround	Time	Shippe	d By	Repo	rt Send Via	:
Company	NV5		Same Day		FedEx		Web		
Address	3777 Long Beach Blvd., Ann	nex Bldg.	1 Day		UPS		Email		
City/State/Zip	Long Beach, Ca 90807		2 Day		USPS		Fax		
Contact	Eric J. Fleming		3 Day		Drop Off		Verbal		
Office Phone	562-495-5777		5 Day		Drop Box		Mail		
Cell			Weekend		Other		Pick up		
Fax	562-495-5877		Special Ins	tructions:					
Email	eric.fleming@nv5.com]						
		PROJECT	INFORMAT	ION					
Project Name:	Building F		PO Number	:					
Project Number:	RSCC-24-12223		Work Order	No.:	-				
Location:	Santa Ana, CA		Sampled By	:	3				
PI	M	CM		MOLD			LEAD		
PLM EPA 600/M4	L-82-020 D NIOSH 74		Sn	ore Tran		Air			
PLM 400 Pt. Cou	nt (<0.25%)	400B 🗆	Та	ore lift		Paint		TILC	_
PLM 1000 Pt. Co	unt (<0.1%)		Bu	lk Sample		Wipe			
			Sv	wab		Soil			
SAMPLE ID	SAMPLE TYPE		LOCATIO	NC		Date	Start Time	Avg	Volume
						Sampled	Stop Time	Flow Rate	(L)
4690	Paint Chip		NA			5/4/2024	NA	NA	NA
4691	Paint Chip		NA			5/4/2024	NA	NA	NA
4692	Paint Chip		NA			5/4/2024	NA	NA	NA
(i)									
Relinquished By:	ho		Received By	\sim	AND				
Printed Name	Eric Flomi		Printed Nam	e Jack	cie TA.	197			
Date/Time:	5-5-24 176		Date/Time:	176	124	0800			
Relinquished By:			Received By	:					
Printed Name			Printed Nam	е					
Date/Time:			Date/Time:					Lab Form	าร



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Building G Location: Santa Ana, CA

Date Sampled: 5/4/2024 Sampled By: Total Samples: 1

Analytical Method: EPA 7420/3050

2458451

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS					
Lab ID	Location/Description	Sample Weight	Lead Concentration		
Client ID	Location/Description	(g)	ppm (mg/kg)		
2458451-001		0.0000	< 000		
4689	Paint Chip	0.0233	< 220		

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



ſ

CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

		(Lab) C	Order No.	24584	51					
	CUSTOMER INF	ORMATIC	ON	Turnaround	Time	Shippe	ed By	Rap	ort Sond Vi	
Company	NV5			Same Dav		FedEx		Wol		a.
Address	3777 Long Beach	Blvd., An	nex Bldg.	1 Day		UPS		Emai		
City/State/Zip	Long Beach, Ca	90807		2 Dav		USPS		Enia		
Contact	Eric J. Fleming			3 Day		Dron Off		Vorba		
Office Phone	562-495-5777			5 Day		Drop Box		Verba		
Cell				Weekend		Other		Dickur		
Fax	562-495-5877			Special Ins	tructions	Touror		FICK UL		
Email	eric.fleming@nv5	.com			doctorio.					
			PROJECT	INFORMAT	ION					
Project Name:	Building G			PO Number						
Project Number:	RSCC-24-12223			Work Order	No.:					_
Location:	Santa Ana, CA			- Sampled By	:		-			
PI	M	1 5	014							
PLM EPA 600/M4	-₩ 1-82-020 □			0.0	MOLD	_	1.000	LEAD	(Pb)	
PLM 400 Pt. Cou	nt (<0.25%)	NIOSH 7	400A 🗆	Sp Ta	ore Irap		Air		TTLC	
PLM 1000 Pt. Co	unt (<0.1%)	w/ TWA		Bu	lk Sample		Wine			
				SV	vab		Soil			
SAMPLE ID	SAMPLE TY	PE		LOCATIO	N		Date	Start Time	Ava	Volume
						~	Sampled	Stop Time	Flow Rate	(L)
4689	Paint Chip			NA			5/4/2024	NA	NA	NA
	1									
,										
Relinquished By:	le le			Received By:	ar	In				
Printed Name	Eric Plan	4.		Printed Name	· Jau	KIETAY.	11			
Date/Time:	5-5-24 120	0		Date/Time:	5/4	124	0800			
Relinquished By:				Received By:						
Printed Name				Printed Name	*					
Date/Time:				Date/Time:					Lab Form	s



Alta Environmental 3777 Long Beach Boulevard Long Beach, CA 90807 Attention: Eric Fleming

Report Number:

Date Received:

Date Analyzed:

Date Reported:

Project Number: RSCC-24-12223 Project Name: Sheds Location: Santa Ana, CA

Date Sampled: 5/4/2024 Sampled By: Total Samples: 2

Analytical Method: EPA 7420/3050

2458462

5/6/2024

5/7/2024

5/7/2024

Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS				
Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)	
2458462-001 5188	Paint Chip	0.0707	< 71	
2458462-002 5189	Paint Chip	0.1024	< 49	

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

abatt

Approved Signatory- Cristina E. Tabatt



CHAIN OF CUSTODY

1508 E. 33rd Street Signal Hill, CA 90755 562-206-2770 Tel 562-206-2773 Fax services@AQenvlabs.com

(Lab) Order No. 2	458462
-------------------	--------

		<u> </u>			_					
	CUSTOMER INFO	RMATION		Turnaround	Time	Ship	oped By	Repor	t Send Via:	
Company	NV5			Same Day		FedEx		Web		
Address	3777 Long Beach	Blvd., Anne	ex Bldg.	1 Day		UPS		Email	P	
City/State/Zip	Long Beach, Ca 9	0807		2 Day		USPS		Fax		
Contact	Eric J. Fleming			3 Day		Drop C)ff 🔽	Verbal		
Office Phone	562-495-5777			5 Day		Drop E	lox 🗆	Mail		- 1 - 1
Cell				Weekend		Other		Pick up		
Fax	562-495-5877			Special In	struction	s:				
Email	eric.fleming@nv5.	com								
			PROJECT	INFORMA	TION	-			_	
Project Name:	Shode		ROJECT	PO Numbe	r.					
Project Name.	BECC 24 12223			Work Orde	r No :				_	
Location:	Santa Ana, CA			Sampled B	V:				5	
Looddon	ound may on			-			_			
PL	.M	PC	M		MOLD	_			(Pb)	_
PLM EPA 600/M4	1-82-020 □	NIOSH 740		S T	pore Irap		Air		TILC	
PLM 400 Pt. Cou	nt (<0.25%)	W/ TWA		B	ulk Samp		Wipe			
1 EW 1000 F & 00	unit (40.178)			5	Swab		Soil			
SAMPLE ID	SAMPLE TY	PE		LOCAT	ION	61	Date	Start Time	Avg	Volume
							Sampled	Stop Time	Flow Rate	(L)
5188	Paint Chip			NA	A		5/4/2024	NA	NA	NA
5189	Paint Chip			N	Ą		5/4/2024	NA	NA	NA
							3			
			31							
Relinquished By:	9/			Received I	By: C	-h-m	8			
Printed Name	E. Flemi	2		Printed Na	me	Jackie	TRY11			
Date/Time:	5-5-24 12	0		Date/Time	:	5/6/21	f 1081	20		
Relinguished By				Received	By:					
Printed Name				Printed Na	ime					
Date/Time:				Date/Time	:				Lab For	ms

Ver. 2016-06-27

N | V | 5

APPENDIX C

Sample Location Map

N | V | 5

Asbestos





NV5

Lead



N | V | 5

APPENDIX D

NV5 Employee and Laboratory Certifications

State of California Division of Occupational Safety and Health Certified Asbestos Consultant

-	Name
	Certification No. 00-2816
frant cont	Expires on 09/22/24
	This certification was issued by the Division o Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.

1



STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:



CERTIFICATE TYPE:NUMBER:EXPIRATION DATE:Lead Inspector/AssessorLRC-0000345410/4/2024Lead Project MonitorLRC-0000345510/4/2024Lead SupervisorLRC-0000345310/4/2024

Eric Fleming

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD

State of California Division of Occupational Safety and Health Certified Asbestos Consultant Christine Jordan







Certificate of Accreditation to ISO/IEC 17025:2017

NVLAP LAB CODE: 500044-0

AQ Environmental Laboratories - Bulk Asbestos Fiber Analysis Signal Hill, CA

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

Asbestos Fiber Analysis

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2024-01-01 through 2024-12-31

Effective Dates



For the National Voluntary Laboratory Accreditation Program





SCOPE OF ACCREDITATION TO ISO/IEC 17025:2017

AQ Environmental Laboratories - Bulk Asbestos Fiber Analysis

1508 E. 33rd Street Signal Hill, CA 90755 Ms. Cristina E. Tabatt Phone: 562-206-2770 Fax: 562-206-2773 Email: ctabatt@aqenvlabs.com

ASBESTOS FIBER ANALYSIS

NVLAP LAB CODE 500044-0

For the National Voluntary Laboratory Accreditation Program





CALIFORNIA STATE

ENVIRONMENTAL LABORATORY ACCREDITATION PROGRAM

CERTIFICATE OF ENVIRONMENTAL LABORATORY ACCREDITATION

Is hereby granted to

AQ Environmental Laboratories, LLC

1508 East 33rd Street

Signal Hill, CA 90755

Scope of the certificate is limited to the "Fields of Accreditation" which accompany this Certificate.

Continued accredited status depends on compliance with applicable laws and regulations, proficiency testing studies, and payment of applicable fees.

This Certificate is granted in accordance with provisions of Section 100825, et seq. of the Health and Safety Code.

Certificate No.: 2823

Effective Date: 9/1/2023

Expiration Date: 8/31/2025

Christine Sotelo, Program Manager Environmental Laboratory Accreditation Program

Sacramento, California subject to forfeiture or revocation



CALIFORNIA STATE ENVIRONMENTAL LABORATORY ACCREDITATION PROGRAM Fields of Accreditation



AQ Environmental Laboratories, LLC

1508 East 33rd Street Signal Hill, CA 90755 Phone: 5622062770 Certificate Number: 2823 Expiration Date: 8/31/2025

Field of Accreditation:114 - Inorganic Constituents in Hazardous Waste					
114.515 001	Lead	EPA 7420			
Field of Accredit	ation:121 - Bulk Asbestos Analysis of Hazardous Waste				
121.010 001	Bulk Asbestos	EPA 600/M4-82-020			

LEAD HAZARD EVALUATION REPORT

Section 1 — Date of Lead Hazard Evaluation 5-4-24				
Section 2 — Type of Lead Hazard Evaluation (Check	one box only)			
Lead Inspection Risk assessment C		Other (specify) Limited pa	int inspection	
Section 3 — Structure Where Lead Hazard Evaluatio	n Was Conducted			
Address [number, street, apartment (if applicable)]	City	County	Zip Code	
2900 West Edinger Ave	Sant Ana	LA	92704	
Construction date (year) Type of structure		Children living in structu	Children living in structure?	
of structure Multi-unit building	School or daycare	🗌 Yes 🖌 N		
Single family dwelling	Other Adult School	Don't Know		
Section 4 — Owner of Structure (if business/agency.	list contact person)			
Name		Telephone number		
Ava Hill (Client)		951-741-4829		
Address [number, street, apartment (if applicable)]	City	State	Zip Code	
2323 North Broadway	Santa Ana	CA	92706	
Section 5 — Results of Lead Hazard Evaluation (che	ck all that apply)	A		
······································	hand we introduce the d	Deterioreted load h	and point detected	
No lead-based paint detected				
No lead hazards detected Lead-contaminated du	ust found Lead-contar	minated soil found	ther	
Section 6 — Individual Conducting Lead Hazard Eva	luation			
Name		Telephone number		
Eric J. Fleming		562-495-5777		
Address [number, street, apartment (if applicable)]	City	State	Zip Code	
3777 Long Beach Blvd., Annex Bldg	Long Beach	CA	90807	
CDPH certification number Signature			Date	
	10		<mark>5-10-24</mark>	
LRC-00003454	6			
LRC-00003454 Name and CDPH certification number of any other individuals of	conducting sampling or testing	(if applicable)		
LRC-00003454 Name and CDPH certification number of any other individuals of	conducting sampling or testing	(if applicable)		
LRC-00003454 Name and CDPH certification number of any other individuals of	conducting sampling or testing	(if applicable)		

C. All data collected, including quality control data, laboratory results, including laboratory name, address, and phone number.

First copy and attachments retained by inspector Second copy and attachments retained by owner Third copy only (no attachments) mailed or faxed to:

California Department of Public Health Childhood Lead Poisoning Prevention Branch Reports 850 Marina Bay Parkway, Building P, Third Floor Richmond, CA 94804-6403 Fax: (510) 620-5656



HAZARDOUS MATERIALS ABATEMENT SPECIFICATION Centennial Education Center Buildings A, B, D, E, F, and Sheds at Portable C110

May 10, 2024

Prepared For:

Rancho Santiago Community College District Ms. Ava Hill 2323 North Broadway Santa Ana, CA 92706



NV5 – Alta Environmental 3777 Long Beach Blvd, Annex Building Long Beach, CA 90807 Phone: 562.495.5777

RSCC-24-12223

NV5

TABLE OF CONTENTS

1.0 F	PART 1 - GENERAL	1
1.1	PROJECT SITE	1
1.2	PROPOSED PROJECT	1
1.3	REMOVAL SCOPE OF WORK	1
1.4	WORK TO BE PERFORMED BY OTHERS	3
1.5	RESPONSIBILITIES OF OWNER	3
1.6	REQUIRED LICENSURE	4
1.7	PERMITS	4
1.8	NOTIFICATIONS	4
1.9		4
1.10	BONDING REQUIREMENTS	4
1.11	PROJECT SCHEDULE	5
1.12		5
1.13	SUBMITIALS	5
1.14		1
1.15		(0
1.10		0
1.11		0
2.0 F	PART 2 - PRODUCTS	9
2.1	MATERIALS	9
2.2	EQUIPMENT	9
3.0 F	PART 3 - EXECUTION1	0
3.1	CLEAN-UP PROCEDURES1	0
3.2	WORKER DECONTAMINATION SYSTEMS1	.1
3.3	DISPOSAL PROCEDURES1	2
3.4	RE-ESTABLISHMENT OF THE WORK AREAS1	.3
3.4	1 Visual Inspection	3
3.4	2 Abatement Clearance Criteria	.3
35		3
3.5	PERSONNEL AIR MONITORING 1	Δ
37	REMOVAL WORK PROCEDURES	5
~ ~ ~		5
3.1	1.1 ROOT WASTIC and ROOTING WATErial (AUW)1	.) 5
3.1 27	.z Leau Faill- Slaviilzalivii1	C.
3.7		0
3.8	ADDITIONAL REGULATORY REQUIREMENTS1	.6

NIV|5

1.0 PART 1 - GENERAL

1.1 PROJECT SITE

Centennial Education Center (CEC), is located on the campus of Santa Ana College/Rancho Santiago Community College District located at 2900 West Edinger Avenue Street, Santa Ana, CA 92704. The work area consists of Buildings A, B, D, E, F, and the Sheds at Portable C110 (Site).

1.2 PROPOSED PROJECT

The scope of work for this project will consist of the removal of identified building related hazardous materials which may be impacted by the renovation project at the Site.

1.3 REMOVAL SCOPE OF WORK

The general intent of this document is to notify the abatement contractor of the minimum requirements for handling, removal, and disposal of asbestos-containing materials (ACM) and lead-containing paints (LCP). Alternative procedures may be used, but the procedures must meet or exceed current federal, state, local and District requirements. Any proposed alternative procedures must be reviewed and approved by District representative prior to implementation of the work.

By submitting a bid, the Contractor warrants its intent to conduct said work properly using qualified personnel employed by licensed contractors.

- A. Scope of work shall include materials impacted prior to renovation project at the various buildings included in above where hazardous materials have been identified, as outlined in the tables below.
- B. All removal and disturbance of asbestos-containing materials (ACM) and subsequent waste disposal shall be performed by an asbestos abatement contractor, using 40-hour asbestos trained workers (Asbestos Worker trained as outlined in 40 CFR 763). Abatement contractor's workforce shall be supervised by experienced trained workers, knowledgeable and qualified in the techniques of asbestos abatement, handling and disposal of asbestoscontaining and/or asbestos-contaminated materials, and the subsequent cleaning of contaminated areas, including, at a minimum, Competent Person/Contractor Supervisor training as outlined in 40 CFR 763.
- C. All removal and disturbance of lead-based paints and subsequent waste disposal shall be performed by a state-licensed contractor, using CDPH-certified workers with at least one CDPH-certified Supervisor. Abatement contractor's workforce shall be supervised by experienced trained workers, knowledgeable and qualified in the techniques of lead abatement, handling and disposal of lead-containing and/or lead-contaminated materials, and the subsequent cleaning of contaminated areas.



- D. All removal and disturbances of lead-containing painted surfaces (reported between 0 and less than 5,000 ppm by paint chip analysis) are subject to Cal/OSHA worker exposure requirements (8 CCR 1532.1) including the use of respirators and protective clothing until the contractor has demonstrated through objective data the exposure levels to lead dust based on a negative exposure assessment do not exceed the permissible exposure level.
- E. When exposure monitoring of a specific lead-related task indicates that the permissible exposure level is or will be exceeded, the contractor shall use CDPH-certified lead workers to complete the task.
- F. Contractor shall furnish all labor, materials, services, insurance (specifically covering the handling and transportation of asbestos and lead which is specified, shown or reasonably implied for the removal, transport, and disposal of the hazardous materials identified in the following table:

SUMMARY OF ASBESTOS-CONTAINING MATERIALS (ACM), ASBESTOS-CONTAINING CONSTRUCTION MATERIALS (ACCM), and MATERIALS WITH A DETECTIBLE AMOUNT OF ASBESTOS

MATERIAL	LOCATION	SCOPE OF IMPACT	ESTIMATED QUANTITY	SPECS SECTION
	B	uilding A		
White and black roof mastic	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	Removal as necessary	*200 SF	3.7.1
	B	uilding B		
White/black roof mastic	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	Removal as necessary	*100 SF	3.7.1
Rolled on roofing	Throughout the roof field	Removal as necessary	*5,500 SF	3.7.1
	B	uilding C		
White/black roof mastic	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	Removal as necessary	*50 SF	3.7.1
Rolled on roofing	Throughout the roof field and patio	Removal as necessary	*3,500 SF	3.7.1
Building D				
White/black roof mastic	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	Removal as necessary	*50 SF	3.7.1
Rolled on roofing	Throughout the roof field	Removal as necessary	*2,500 SF	3.7.1

NIV|5

MATERIAL	LOCATION	SCOPE OF IMPACT	ESTIMATED QUANTITY	SPECS SECTION
	В	uilding E		
White and black roof mastic	At all penetrations, pads, perimeter of the parapet wall, on flashing, and on conduit and pipe	Removal as necessary	*200 SF	3.7.1
Rolled on roofing	Throughout roof field on both levels	Removal as necessary	*9,000 SF	3.7.1
Building F				
White and black roof mastic	At all penetrations, pads, perimeter of the parapet wall, and on conduit and pipe	Removal as necessary	*200 SF	3.7.1
Rolled on roofing	Throughout roof field	Removal as necessary	*6,500 SF	3.7.1
Sheds				
Rolled on roofing	Throughout roof field	Removal as necessary	8100 SF	3.7.1
* Project may not impact all roofing. Contractor is responsible for quantifying amount of material to be removed				

SUMMARY OF LEAD-CONTAINING PAINT

COMPONENT	LOCATION	SCOPE OF IMPACT	SPECS SECTION
Flashing	Building B - Perimeter of	Removal as necessary	3.7.2 or
	building and visual barriers	······	3.7.3
Visual barrier	Building D - Inner and outer	Removal as necessary	3.7.2 or
	walls of visual barrier	Removal as necessary	3.7.3
Flashing	Building E - Perimeter of	Romoval as popossan/	3.7.2 or
	building and visual barriers	Removal as necessary	3.7.3
Project may not impact all material. Contractor is responsible for quantifying amount of material to be			

removed

1.4 WORK TO BE PERFORMED BY OTHERS

As per project specifications and approved abatement plan submittal.

1.5 **RESPONSIBILITIES OF OWNER**

The Owner will provide daily oversight and environmental monitoring surrounding the abatement/removal operations.
NIV 5

1.6 **REQUIRED LICENSURE**

- A. Contractor shall be licensed by the State of California, Contractors State License Board and be registered to perform asbestos related work with the Division of Occupational Safety and Health, Department of Industrial Relations. At a minimum contractor shall hold the following license classification:
 - a. ASB Asbestos Certification
 - b. C-22 Asbestos Abatement Contractor Classification
- B. Transportation of Friable and Non-Friable Asbestos Containing Materials: Contractor shall itself be or have a subcontractor who is a registered hazardous waste transporter with the State of California, Department of Toxic Substances Control.
- C. The Contractor shall ensure all workers performing specific tasks are properly certified and trained to perform said tasks.
- D. Subcontractors shall hold all licenses applicable to specified trade work.

1.7 PERMITS

- A. As required by California Division of Occupational Safety and Health (Cal/OSHA)
- B. As required by the South Coast Air Quality Management District (SCAQMD)
- C. As required by Department of Health Services (Cal/DPH)
- D. As required by local agencies for specific tasks (i.e., temporary power, etc.)

1.8 NOTIFICATIONS

- A. Contractor shall make all required written notifications to regulatory agencies including the following:
 - a. Cal/OSHA
 - b. SCAQMD
 - c. Cal/DPH
 - d. Local Agencies, as required
 - e. District prior to submittal

1.9 INSURANCE REQUIREMENTS

A. Provide as per Project Specifications.

1.10 BONDING REQUIREMENTS

A. Provide As per Project Specifications.

N|V|5

1.11 PROJECT SCHEDULE

A. Project Start Date: As specified by Owner

Project Completion Date: As specified by Owner

B. All work shall be performed as per agreement between Contractor and Owner.

1.12 APPLICABLE REGULATIONS

- A. Contractor shall perform all Work in compliance with current, applicable federal, state, and local regulations, standards and codes including District specifications governing asbestos abatement, transport, and disposal of asbestos containing/contaminated materials, leadbased/containing surface coatings and contaminated materials, and all other hazardous materials.
 - a. Requirements include obtaining permits, licenses, inspections, releases and similar documentation, as well as payments, statements and similar requirements associated with codes, regulations, and standards.
- B. Regulations, Standards, and Codes (General):
 - a. General applicability of federal, state, and local regulations, standards and codes governing hazardous materials abatement, demolition, transport, and disposal, except to the extent that more explicit or more stringent requirements are written directly into the contract documents, all applicable regulations, standards, and codes have the same force and effect and are made a part of the contract documents as if copied directly into the contract documents, or as if published copies are bound herewith.
- C. Contractor Responsibility: The Contractor shall assume full responsibility and liability for the compliance with all applicable federal, state, and local regulations including District specifications pertaining to work practices, transport, disposal, and protection of workers, visitors to the site, and persons occupying areas adjacent to the site.
 - a. The contractor is responsible for providing training, medical examination and maintaining training/medical records of personnel as required by the applicable federal, state, and local regulations.

1.13 SUBMITTALS

- A. Prior to commencement of work, Contractor shall submit to the Project Environmental Consultant (Owner's Representative) documentation that includes, without limitation, the following:
 - a. A detailed abatement plan outlining the scope of work and means/methods to be used for the duration of the project.



- b. Copies of licenses and registrations required by Article 1.6 Required Licensure (include copies of subcontractors' licenses).
- c. Copies of written notification to the following regulatory agencies:
 - I. Cal/OSHA
 - II. SCAQMD
 - III. Cal/DPH
 - IV. Local agencies, as applicable
 - V. The District
- d. Manufacturer's certification that HEPA vacuums, differential pressure air filtration devices and other local exhaust ventilation equipment conform to ANSI Z9.2-79 and have been permitted by the SCAQMD. Applicable portable equipment registration program (PERP) certification(s) shall also be provided.
- e. Documentation showing that Contractor's employees, including foreman, supervisor, and any other company personnel or agents who may be exposed to airborne asbestos fibers or who may be responsible for any aspects of asbestos abatement activities, have received training as required by 29 CFR 1926.1101 and 8 CCR 1529.
- f. Documentation showing that Contractor's employees, including foreman, supervisor, and any other company personnel or agents who may be exposed to airborne lead dust or who may be responsible for any aspects of lead abatement activities, have received training as required by 29 CFR 1926.62 and 8 CCR 1532.1.
- g. Documentation from Physician (signed by an M.D.) showing that all employees or agents who may be exposed to airborne asbestos fibers in excess of background levels have received medical monitoring to determine whether they are physically capable of working while wearing the respirator required without suffering adverse health effects. The Contractor must be aware of and provide information to the examining physician about unusual conditions in the workplace environment (e.g. high temperatures, humidity, chemical contaminants) that may impact on the employee's ability to perform work activities.
- h. Documentation of respirator fit testing for all Contractor employees and agents who must enter the work area. This fit testing shall be conducted annually and in accordance with procedures as required by 29 CFR 1910.134 and 8 CCR 5144.
- i. Contractor's Health and Safety Plan, including an emergency preparedness plan as required by Article 1.16 Emergency Planning.
- j. Contractor's Respiratory Protection Plan
- k. Contractor's Injury and Illness Prevention Plan (IIPP)
- I. Contractor's lead waste profile sampling plan
- m. Copies of SDSs for materials to be used on site



B. During abatement activities, Contractor shall maintain on-site records and submit to Project Environmental Consultant at the completion of the project documentation that includes, without limitation, the following:

Copies of the work area entry/exit log book.

Copies of logs documenting filter changes on respirators, HEPA vacuums, differential pressure air filtration devices, water filtration device, and other engineering controls.

Copies of Safety Data Sheets (SDS) for solvents, encapsulants, wetting agents, replacement materials, and other substances brought by Contractor to the Project Site. SDSs shall be available the first day that subject materials/substances are present on the project site.

Results of all required OSHA compliance air monitoring. Results shall be available for review by Consultant and Owner within 24 hours the sampling.

Copies of all accident/incident reports where injury or damage has occurred on or to the Owner's property.

Copies of daily logs indicating location(s) worked, type of materials removed, quantity of materials removed and number of personnel conducting the aforementioned activities.

Copies of all transport manifests, trip tickets and disposal receipts for all asbestos waste materials removed from the site.

1.14 NOTICES

- A. Post in the clean room area of the worker decontamination enclosure a list containing the names, and telephone numbers of Owner, Construction Manager, Abatement Contractor, and Project Environmental Consultant.
- B. Additional postings shall include:
 - a. Visitor Entry and Exit Log.
 - b. Employee Daily Sign in Log.
 - c. Entry and Exit Procedures.
 - d. Emergency Procedures.
 - e. Copies of permits required in Article 1.7 of this document and copies of notifications required in Article 1.8 of this document.
 - f. As required by the Department of Labor.

1.15 SITE USE AND SECURITY

- A. Confine operations at the site to the areas permitted under the Contract. Portions of the site beyond areas on which work is indicated are not to be disturbed.
- B. The work area shall be restricted only to authorized, trained, and protected personnel, including Contractor, Contractor's employees, Owner's employees, Owner, Construction Manager, Project Environmental Consultant, State and Local Inspectors.



- C. Entry into the work area by unauthorized individuals shall be reported immediately to the Project Environmental Consultant.
- D. Contractor shall be responsible for Project site security during abatement operations.
- E. Contractor shall take meal and other breaks in areas not used by students.

1.16 EMERGENCY PLANNING

- A. Emergency planning and procedures shall be developed by Contractor prior to abatement initiation.
- B. Emergency procedures shall be in written form and prominently posted. Contractor shall ensure that all persons entering the work area read these procedures and understand the Project site layout, location of emergency exits and emergency procedures.
- C. Emergency planning shall include considerations of fire, explosion, electrical hazards, slips, trips and falls, confined spaces, and heat related injury. Written procedures shall be developed and employee training in procedures shall be provided by Contractor.
- D. Employees shall be trained in evacuation procedures in the event of workplace emergencies.
 - a. For non-life-threatening situations, employees injured or otherwise incapacitated shall decontaminate following normal procedures with assistance from fellow workers, if necessary, before exiting the work place to obtain proper medical treatment.
 - b. For life threatening injury or illness, worker decontamination shall take least priority. After measures to stabilize the injured worker, remove him from the work place and secure proper medical treatment.
 - c. Telephone numbers of all emergency response personnel shall be prominently posted in the clean and equipment rooms.

1.17 FIRE PROTECTION

- A. All plastic, spray-on strippable coatings, and structural materials used in the asbestos abatement process shall be UL-approved and certified as fire retardant or noncombustible.
- B. Wood shall be pressure impregnable and certified as fire retardant.
- C. Safety Data Sheets (SDS) for fire retardant materials shall be made available upon request.
- D. All combustible rubbish and debris, including asbestos waste shall be properly packaged, labeled and stored in a District designated lockable storage facility at the end of each working day.
- E. A minimum of one (1) 4A/60BC dry-chemical extinguisher shall be maintained at each of the following locations:



- a. At each corner of the work area. Where no clear corners exist, four (4) extinguishers shall be placed around the exterior wall of the work area so that they are approximately 25 percent of the total distance apart.
- Exception: Where total contained work area is less than 1,000 square feet, two (2) 4A/60BC extinguishers shall be provided. All extinguishers shall be clearly identified with red tape.
- F. Contractor shall ensure that on site personnel are aware of the location and proper use of all extinguishers and other fire/life safety equipment.
- G. All existing fire detection, alarm systems, connections and standpipes shall remain in place, active and unobstructed. Any alteration to this equipment must be approved by the Owner.

2.0 PART 2 - PRODUCTS

2.1 MATERIALS

- A. Generally, Contractor shall carefully adhere to the following:
 - a. All plastic, spray-on strippable coatings and structural materials used shall be ULcertified as fire retardant or non-combustible.
 - b. Fire-retardant polyethylene sheeting utilized for worker decontamination and construction/containment barriers shall be a minimum of six-mil in thickness.
 - c. Disposal bags used to package hazardous waste shall be of six-mil polyethylene, pre-printed with labels as required by EPA regulation 40 CFR 61.152 (b) and 8 CCR 1529.
 - d. Warning signs as required by Cal/OSHA shall be utilized.
- B. Removal and Encapsulation:
 - a. Apply surfactant during removal work activities.
 - b. Apply an encapsulating agent to the substrate surfaces from which asbestoscontaining material has been stripped.
 - c. Mastic removal solvents shall be of the low odor variety.

2.2 EQUIPMENT

- A. General:
 - a. A sufficient number of HEPA vacuums and/or differential pressure air filtration devices equipped with HEPA filtration shall be used to control asbestos fibers during the removal of asbestos containing materials. To calculate total air flow requirement:

NV5

Total ft³/min = $\frac{\text{Vol. of work area (in ft^3)}}{15 \text{ min}}$

To calculate the number of units needed for the abatement:

Number of units needed = <u>[total ft³/min]</u> [capacity of unit in ft³/min]

- b. At a minimum, full-face powered air-purifying respirators (PAPRs) equipped with HEPA filters cartridges shall be utilized during all friable/Class I asbestos removal and for all removal of lead-containing paints/substances involving abrasive removal techniques.
- c. At a minimum, half-face air-purifying respirators with P-100 cartridges shall be utilized for the removal of all non-friable/Class II asbestos removal, and lead coated, ceramic tile, and impacted damaged lead-based paint except abrasive removal.
- d. Respirators shall be furnished to the abatement workers by Contractor. The respirators shall have been tested and approved by National Institute of Occupational Safety and Health (NIOSH) for use in asbestos-contaminated atmospheres.
- e. Full body disposable protective clothing, including head, body, and foot coverings shall be furnished to workers and visitors by the abatement contractor. The clothing shall include adequate sizes to accommodate movement without tearing.
- f. Additional safety equipment as supplied in accordance with 8 CCR 1514, (e.g. hard hats meeting the requirements of 8 CCR 1515, eye protection meeting the requirements of 8 CCR 1516, safety shoes meeting the requirements of 8 CCR 1517, hand protection meeting the requirements of 8 CCR 1521 and body protection meeting the requirements of 8 CCR 1521 and body protection meeting the requirements of 8 CCR 1522), as necessary, shall be furnished to all workers and authorized visitors.
- B. Removal:
 - a. Removal shall be performed using manual means and methods. Perform removal in manageable section and perform continuous clean-up of debris. Mechanical removal shall only be performed in conjunction with Owner approved HEPA air filtration systems.
 - b. Perform detail cleaning using HEPA vacuuming and wet wiping methods. No brooms shall be used during asbestos and lead-based paint related work.
- C. Encapsulation: Encapsulants shall be sprayed using airless spray equipment or a hand pressurized sprayer.

3.0 PART 3 - EXECUTION

3.1 CLEAN-UP PROCEDURES

A. Remove and containerize all visible accumulations of asbestos-containing material, and asbestos/lead-contaminated debris utilizing rubber dust pans and rubber squeegees to



move material around. Do not use metal shovels to pick up or move accumulated waste within contained work areas.

- a. Asbestos-containing/contaminated waste shall be packaged and label in accordance with EPA regulation 40 CFR 61.152 (b) (l) (iv), Cal/OSHA (Title 8 CCR Sections 1529 and 5208), SCAQMD Rule 1403, and if applicable Title 22 CCR Section 66504.
- b. Lead-waste wastes shall be packaged, and label as required by 8 CCR 1532.1 and 22 CCR 66504.
- c. All other hazardous wastes shall be containerized as appropriate and disposed of in a manner that satisfies the requirements for waste characterization and disposal in accordance with the requirements of Title 22 of the California Code of Regulations, Sections 66243, et seq., and Sections 25157.8, et al, of the California Health and Safety Code.
- B. Whether cleaning an asbestos work area or a lead work area (or both), wet clean all surfaces in the work area using a HEPA-vacuum, as appropriate.
- C. After gross cleaning of the work area, HEPA-vacuum and wet clean all objects and surfaces in the work area are completed, remove all containerized waste from the work area.
- D. Decontaminate all tools and equipment and remove at the appropriate time in the cleaning sequence.
- E. Project Environmental Consultant and the abatement contractor representative will inspect the work area for visible residue. If any accumulation of residue is observed, a second settling period and cleaning cycle repeated at no additional cost to Owner.
- F. Following the satisfactory completion of clearance air monitoring or clearance wipe testing, the remaining barriers may be removed and prepared for proper disposal. A final visual inspection by Project Environmental Consultant and the abatement contractor representative will be performed. Unsatisfactory conditions may require additional cleaning and air monitoring/wipe sampling, at no additional cost to Owner.

3.2 WORKER DECONTAMINATION SYSTEMS

- A. Worker decontamination enclosure systems shall be provided at all locations where workers will enter or exit regulated work areas.
- B. Worker decontamination enclosure systems constructed at the Project site shall utilize six-mil, fire-retardant polyethylene sheeting, or other approved materials for privacy.
- C. Personnel Decontamination Units shall not be located inside the work area(s) unless specifically authorized by the Project Environmental Consultant.
- D. Alternate methods of providing Decontamination facilities may be submitted to the Project Environmental Consultant for approval. Do not proceed with any such method(s) without the written authorization.



E. The worker decontamination enclosure system shall consist of at least a cleansing station in accordance with the requirements of 8 CCR 1527 and 8 CCR 1529, equipped with adequate water, towels and cleansing agents to accommodate the entire crew and visitors.

3.3 DISPOSAL PROCEDURES

- A. All Class I friable asbestos waste shall be disposed as hazardous, waste and disposed at an appropriate landfill facility. The waste shall be manifested using a Uniform Hazardous Waste Manifest.
- B. All Class II non-friable asbestos waste shall be disposed of as Non-Hazardous, Non-Friable Asbestos Waste. A non-hazardous material data form will be required.
- C. All asbestos-containing waste shall be placed and stored in clear, sealed, leak-tight and appropriately labeled containers, in accordance with 8 CCR 1529 and SCAQMD Rule 1403, and transported to an appropriate landfill for disposal.
- D. The abatement contractor will be responsible for segregating lead waste (LBP and LCP) into separate waste streams. The contractor will be required to collect a sufficient number of samples to adequately characterize the waste stream. Sample analysis will include at a minimum, Total Threshold Limit Concentration (TTLC), Soluble Threshold Limit Concentration (STLC) and Toxicity Characteristic Leaching Procedure (TCLP).

The contractor shall develop and submit for review a waste sampling and management plan to the Owner and the Project Environmental Consultant.

- E. All hazardous wastes (including non-hazardous asbestos wastes) must be transported by a certified waste hauler and disposed of at a waste facility approved by the Owner.
- F. Obtain the EPA Hazardous Waste Generator Identification Number and State of California Hazardous Waste Tax Identification Number from the Owner for hazardous waste disposal.
- G. All hazardous waste manifests, non-hazardous manifest, and tonnage forms shall be delivered to the owner within 14 business days. Record keeping format shall utilize a chain of custody form which includes the names and addresses of the Generator (Owner), Contractor, Waste Hauler, pickup site, disposal site, the estimated quantity of the asbestos waste and the type of containers used. The form shall be signed by the Generator, Contractor, Waste Hauler and the Disposal Site Operator, as the responsibility for the material changes hands.
- H. In addition to the above the following will need to take place:
 - a. Field info regarding friability of waste and laboratory data characterizing any waste streams and associated reports that discuss whether waste streams are hazardous or non-hazardous and why
 - b. Provide the laboratory data and report to proposed receiving facility, so that the receiving facility can provide a "waste acceptance" letter.



- c. Prepare a draft manifest for District Facilities' review
- d. Provide lab data, report, "waste acceptance letter", transporter EPA ID for hazardous waste shipments, and populated draft manifest to Facilities for review and approval prior to disposal.
- e. Provide facility weigh tickets from the receiving facilities for loads taken to the receiving facilities for tracking and tax purposes within 14 business days.

The contractor shall develop and submit for review a waste sampling and management plan to the Owner and the Project Environmental Consultant.

3.4 RE-ESTABLISHMENT OF THE WORK AREAS

3.4.1 Visual Inspection

Upon completion of the removal process, the Owner Representative and the abatement contractor will conduct a post-abatement visual inspection. Any material that is to be left in place for any reason shall be thoroughly encapsulated and/or stabilized. If any material designated for removal, including loose debris, is observed, the Contractor will be required to re-clean that specific area.

3.4.2 Abatement Clearance Criteria

- A. Following the completion of final clean-up operations, notify the Project Environmental Consultant that work areas are ready for final inspection and clearance air monitoring.
- B. Project Environmental Consultant will then sample the air in the work area for airborne fiber concentrations as necessary. Sampling will be completed in accordance with Phase Contrast Microscopy (PCM) NIOSH Method 7400.
 - a. Using the NIOSH 7400 method, samples from inside the work area will be collected. Clearance will be issued when samples results show that the airborne fiber concentrations inside the abatement work areas are equal to or less than 0.01f/cc or the background level, whichever is greater.
- C. If these conditions are not met, decontamination shall be deemed incomplete, and the cleaning procedures shall be repeated. The area shall be re-cleaned and re-tested at no additional cost to Owner until satisfactory levels are obtained.
- D. For lead paint removal clearance will be achieved by a thorough final visual inspection.

3.5 ENVIRONMENTAL MONITORING

A. Air monitoring will be carried out by the Project Environmental Consultant on behalf of the Owner to verify that the building beyond the contamination area and the outside environment remains uncontaminated.



- B. Area Air Monitoring: The Project Environmental Consultant will conduct in-progress air monitoring daily to determine area airborne contaminant concentrations within the confines of the work area.
 - a. Environmental Air Sampling: Ambient air samples are taken and analyzed to indicate fiber migration from containment to the environment. Should any environmental sample outside work areas exceed the base line of 0.01 f/cc of air or established background concentrations as determined by PCM analysis, all work will immediately halt except for corrective work. The Project Environmental Consultant shall determine the source of the high fiber count and notify the contractor with directions for corrective action.

3.6 PERSONNEL AIR MONITORING

Air monitoring required by Cal/OSHA is the responsibility of the contractor. The contractor is responsible for providing daily Cal/OSHA compliance monitoring as per 8 CCR 1529 for asbestos and CCR 1532.1 for lead.

- A. At minimum, Contractor shall conduct representative breathing zone personal air monitoring of its employees and repeated daily or until a "negative exposure assessment", as derived in accordance with 29 CFR 1926.1101 (f)(2)(iii) and 8 CCR 1529 for asbestos.
- B. Employers must assess the amounts of lead breathed by workers on a regular basis for each trigger task as per 8 CCR 1532.1. This is usually done by employee breathing zone air sampling. Air sampling results are used to determine the protective measures needed as well as the type of respirator that must be worn for protection.
 - a) Level 1 trigger tasks Any of the following with lead-containing coatings or materials: spray painting, manual demolition, manual scraping or sanding, use of heat gun, power tool cleaning with dust collection system. Minimum required respirator: half-mask respirator with N-100, R-100 or P-100 filters.
 - b) Level 2 trigger tasks Any of the following with lead-containing coatings or materials: using lead-containing mortar, lead burning, rivet busting, power tool cleaning without dust collection system, clean-up activities using dry expendable abrasives, abrasive blasting enclosure movement or removal. Minimum required respirator: air-supplied hood or helmet, or loose fitting hood or helmet powered air purifying respirator with N-100, R-100 or P-100 filters.
 - c) Level 3 trigger tasks Abrasive blasting, welding, cutting, or torch burning on structures where lead-containing coatings or materials are present. Minimum required respirator: half-mask supplied air respirator operated in a positive pressure mode.
- A. Monitoring shall be conducted by a qualified air professional experienced and knowledgeable about the methods of air monitoring and in accordance with 29 CFR 1926.1101, 8 CCR 1529 and 8 CCR 1532.1.

NIV 5

3.7 REMOVAL WORK PROCEDURES

3.7.1 Roof Mastic and Roofing Material (ACM)

Engineering Controls:

1. Establish critical barriers as necessary to prevent contamination outside of the regulated area. A one-stage decontamination facility is required with wash station. Install drop floors around the perimeter of the building to extend at least 10 feet beyond the edge, where applicable.

Min. Resp. Protection:

1. Half face air purifying respirators (APR) with P100 filters are required; provide personal monitoring and comply with Cal/OSHA requirements at all times.

Removal:

1. Remove the material by manual means and methods. Allow surfactant to soak into material and remove in manageable sections. Mechanical removal is not allowed.

Preparation/Transport:

1. Package and label the waste immediately. Store all waste in a lockable storage dumpster.

Disposal:

1. Dispose of waste as non-friable, non-hazardous asbestos-containing waste. A Non-Hazardous Waste Shipment Record is required.

3.7.2 Lead Paint- Stabilization

The procedures below have been prepared with the assumption that removal of lead paint from selected components will be required. The bidding contractor is responsible to fully review, understand, and quantify the removal scope of work prior to submitting the bid.

Engineering Controls:

1. Install demarcation signage and critical barriers. A one-stage decontamination facility with a wash station is required.

Min. Personal Protection:

1. Half-face, air-purifying respirators equipped with HEPA-P100 filters. Disposable clothing (Tyvek® suits, or equivalent) and hand, foot, and eye protection are required. Provide personal monitoring and comply with Cal/OSHA requirements during work activities.

Removal:

1. Wet the work area surfaces and remove any damaged loose and flaky paint. Work performed under this task shall be completed using manual means.

Preparation/Transport:

1. Package and separate the waste into waste streams. Conduct the required waste characterization for disposal. (Refer to Section 3.3 of this document).



Disposal:

1. Dispose of all lead waste in accordance with Federal, State, and Local regulations

3.7.3 Lead Paint – Component Removal

Engineering Controls:

1. Install demarcation signage, drop sheets, and critical barriers as necessary. A one-stage decontamination facility with a wash station is required.

Min. Personal Protection:

1. Half-face, air-purifying respirators equipped with HEPA-P100 filters. Provide personal monitoring and comply with Cal/OSHA requirements during work activities.

Removal:

1. Remove the materials using wet methods. No power equipment without a local exhaust HEPA filter capture. Remove all component using manual means and wet methods.

Preparation/Transport:

1. Package and separate into waste streams. Conduct the required waste characterization for disposal. (Refer to Section 3.3 of this document).

Disposal:

1. Dispose of all lead waste in accordance with Federal, State, and Local regulations.

3.8 ADDITIONAL REGULATORY REQUIREMENTS

Procedures for impacting lead-containing paints (LCP) are not included in this abatement plan but remain subject to regulation. All construction work activities impacting lead-containing paints (LCP) (paints reported below 5,000 ppm) completed for this project, such as but not limited to renovation, removal, renovation etc. remain subject to Cal/OSHA worker exposure requirements (8 CCR 1532.1) including the use of respirators, protective clothing, training, air monitoring, waste disposal, etc. Further, it is the Contractors responsibility to ensure that his workers are adequately protected to potential lead exposure during the initial monitoring period. It is the responsibility of the contractor to fully comply with the requirements of the Cal/OSHA regulation. Cal/OSHA requirements are summarized below:

- a. Employers must assess the concentration of lead breathed by workers on a regular basis for each trigger task as per Section 1532.1(d). This is usually done by employee breathing zone air sampling. Air sampling results are used to determine the protective measures needed as well as the type of respirator that must be worn for protection.
 - i. Level 1 trigger tasks Any of the following with lead-containing coatings or materials: spray painting, manual demolition, manual scraping or sanding, use of heat gun, power tool cleaning with dust collection system. Minimum required respirator: half-mask respirator with N-100, R-100 or P-100 filters.
 - ii. **Level 2 trigger tasks** Any of the following with lead-containing coatings or materials: using lead-containing mortar, lead burning, rivet busting, power tool

N V 5

cleaning without dust collection system, clean-up activities using dry expendable abrasives, abrasive blasting enclosure movement or removal. Minimum required respirator: air-supplied hood or helmet, or loose fitting hood or helmet powered air purifying respirator with N-100, R-100 or P-100 filters.

iii. **Level 3 trigger tasks** – Abrasive blasting, welding, cutting, or torch burning on structures where lead-containing coatings or materials are present. Minimum required respirator: half-mask supplied air respirator operated in a positive pressure mode.

All lead waste shall be segregated into separate waste streams. The contractor will be required to collect a sufficient number of samples to adequately characterize the waste stream. Sample analysis will include at a minimum, Total Threshold Limit Concentration (TTLC), Soluble Threshold Limit Concentration (STLC) and Toxicity Characteristic Leaching Procedure (TCLP). Refer to Section 3.3 for additional information.

End of Section

